

# **DISTRIBUTION OF QUANTITIES**

## Table of Contents - Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583  
 Estimate Name - Advertising  
 R.I. Contract No. - 2018-CB-109  
 FAP Nos: 405-421-891

ItemCode	Description	Page
201.0403	REMOVE AND DISPOSE SIDEWALKS	1
201.0407	REMOVE AND DISPOSE PAVEMENT AND RIGID BASE	1
201.0450	REMOVE AND STOCKPILE ON SITE GRANITE CURB	1
201.0610	REMOVE AND DISPOSE DIRECTIONAL, WARNING, REGULATORY, SERVICE, AND STREET SIGNS	1
201.0617	REMOVE AND DISPOSE CONDUIT - ALL SIZES	1
202.0100	EARTH EXCAVATION	1
203.0100	STRUCTURAL EXCAVATION EARTH	2
203.0700	PERVIOUS FILL	2
204.0100	TRIMMING AND FINE GRADING	2
207.0206	SAND BAG EROSION DIKE STANDARD 9.6.0	2
209.9901	INLET PROTECTION	3
212.2000	CLEANING AND MAINTENANCE OF EROSION CONTROLS	3
301.0300	CRUSHED STONE OR CRUSHED GRAVEL BASE MODIFIED	3
302.0100	GRAVEL BORROW SUBBASE COURSE	3
401.1000	CLASS 19.0 HMA	3
401.2000	CLASS 12.5 HMA	4
403.0300	ASPHALT EMULSION TACK COAT	4
708.9040	CLEANING AND FLUSHING PIPE ALL SIZES	4
708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	4
803.0300	PARTIAL REMOVAL AND DISPOSAL OF EXISTING CONCRETE MASONRY	4
808.0505	CONCRETE SUBSTRUCTURE CLASS HP 3/4'' WALL STEMS	5
808.0601	CONCRETE SUBSTRUCTURE CLASS HP 3/4'' PIERS, COL, CAP	5
808.9901	FIBER WRAP BRIDGE 577 PIER 1 FOR STRENGTHENING	5
808.9902	FIBER WRAP BRIDGE 577 PIER 1 FOR PROTECTION	5
810.0210	GALVANIZED BAR REINFORCEMENT GRADE 60	6
817.2100	REPAIRS TO STRUCTURAL CONCRETE MASONRY (PNEUMATIC MORTAR)	6
817.2110	REPAIRS TO STRUCTURAL CONCRETE MASONRY (PATCHING MORTAR)	6
817.2140	REPAIRS TO STRUCTURAL CONCRETE MASONRY FORM AND CAST IN PLACE	6
819.0800	DRILL AND GROUT REINFORCING DOWELS	6
819.9901	ADHESIVE ANCHOR FOR DOWEL BARS (1-1/4")	6
820.0110	CONCRETE SURFACE TREATMENT (PROTECTIVE COATING)	7
824.9901	TEMPORARY JACKING AND SHORING OF BEAMS BRIDGE 579 PIER 3	7
824.9902	TEMPORARY JACKING AND SHORING OF BEAMS BRIDGE 579 PIER 6	7
824.9903	TEMPORARY JACKING AND SHORING OF BEAMS BRIDGE 583 PIER 5	7
824.9904	TEMPORARY JACKING AND SHORING OF BEAMS BRIDGE 583 PIER 6	7
828.9901	REMOVE STOCKPILE AND REINSTALL 4 BAR RAIL	8
836.0100	STRUCTURAL CONCRETE CRACK REPAIR BY EPOXY-RESIN BASE ADHESIVE INJECTION	8
903.0410	TEMPORARY CHAIN LINK FENCE	8
903.0411	TEMPORARY CHAIN LINK GATE	8
904.0101	REMOVE AND RESET FENCE AND/OR RAILING CHAIN LINK	9
905.0110	PORTLAND CEMENT SIDEWALK MONOLITHIC STANDARD 43.1.0	9
906.0112	GRANITE CURB PROVIDENCE STANDARD 7" STRAIGHT	9
906.0700	REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT, CIRCULAR ALL TYPES	9
906.9901	6'-0" GRANITE TRANSITION CURB STANDARD 7.3.2 MODIFIED, 7" WIDTH	9
906.9902	GRANITE WHEELCHAIR RAMP TRANSITION CURB MODIFIED, 7" WIDTH	10
906.9903	GRANITE RAMP STONE STRAIGHT STANDARD 7.3.9 MODIFIED, 7" WIDTH	10
914.5010	FLAGPERSONS	10
914.5020	FLAGPERSONS - OVERTIME	10

## Table of Contents - Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583  
 Estimate Name - Advertising  
 R.I. Contract No. - 2018-CB-109  
 FAP Nos: 405-421-891

ItemCode	Description	Page
916.9901	NARROW CONDITION IMPACT ATTENUATOR FOR TRAFFIC CONTROL	10
920.0055	PLACED STONE RIPRAP R-3, R-4, R-5 STANDARD 8.3.0	10
922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	11
923.0105	DRUM BARRICADE STANDARD 26.2.0	11
923.0120	PLASTIC PIPE BARRICADE STANDARD 26.3.0	12
923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	12
926.0110	ANCHORED SINGLE-FACE PRECAST CONCRETE BARRIER FOR TEMPORARY TRAFFIC CONTROL	12
928.9901	SHADOW OR ADVANCED WARNING VEHICLE WITH IMPACT ATTENUATOR AND FLASHING ARROW BOARD OR CHANGEABLE MESSAGE SIGN	12
929.0110	FIELD OFFICE	12
932.0210	FULL DEPTH SAWCUT OF BITUMINOUS PAVEMENT AND RIGID BASE	13
932.0230	FULL DEPTH SAWCUT OF PORTLAND CEMENT CONCRETE SIDEWALK/DRIVEWAY	13
936.0110	MOBILIZATION	13
937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	13
942.0200	DETECTABLE WARNING PANEL STANDARD 48.1.0	13
T04.6902	'2' STRANDED COPPER CONDUCTOR 600V INSULATION	13
T04.6906	'6' STRANDED COPPER CONDUCTOR 600V INSULATION	14
T04.6910	'10' STRANDED COPPER CONDUCTOR 600V INSULATION	14
T04.7300	IN-LINE FUSED DISCONNECT DEVICE WITH FUSE WEATHERPROOF	14
T04.7400	IN-LINE UNFUSED DISCONNECT DEVICE	14
T04.7500	SPLICE KIT	15
T05.0100	PRECAST TYPE A HANDHOLE STANDARD 18.2.0	15
T05.1030	ADJUST HANDHOLE TO GRADE	15
T06.5130	3 INCH SCHEDULE 40 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDERGROUND	15
T08.1700	REMOVE AND RELOCATE LIGHT STANDARD	15
T08.9901	LIGHT STANDARD FOUNDATION WITH ANCHOR BOLTS STANDARD 18.1.0	15
T08.9902	ORNAMENTAL POLE/LUMINAIRE - REMOVAL, TEMPORARY INSTALLATION PERMANENT & RE-INSTALLATION	16
T15.0100	DIRECTIONAL REGULATORY AND WARNING SIGNS	16
T20.1000	REMOVE EXISTING PAVEMENT MARKINGS	16
T20.1010	REMOVE EXISTING PAVEMENT MARKINGS	16
T20.2004	4 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	17
T20.2012	12 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	17
T20.2014	4 INCH EPOXY RESIN PAVEMENT MARKINGS YELLOW	17
T20.2020	EPOXY RESIN PAVEMENT ARROW - STRAIGHT, LEFT, RIGHT, OR COMBINED STANDARD 20.1.0	17
T20.2022	EPOXY RESIN PAVEMENT MARKING WORD "ONLY" STANDARD 20.1.0	17
T20.2204	4 INCH TEMPORARY EPOXY RESIN PAVEMENT MARKINGS WHITE	18
T20.2234	TEMPORARY EPOXY RESIN PAVEMENT MARKING - YIELD LINE SYMBOL	18
T20.2304	4 INCH TEMPORARY EPOXY RESIN PAVEMENT MARKINGS YELLOW	18

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
001	201.0403	<b>REMOVE AND DISPOSE SIDEWALKS</b>	<b>SY</b>			
		BRIDGE NO 583				
		SIDEWALK NEAR PIER 5		30.00	0014	01
<b>Item 201.0403 Total:</b>				<b>30.00</b>		
002	201.0407	<b>REMOVE AND DISPOSE PAVEMENT AND RIGID BASE</b>	<b>SY</b>			
		BRIDGE NO 583				
		PROMENADE STREET		20.00	0014	01
		PROVIDENCE PLACE		30.00	0014	01
<b>Item 201.0407 Total:</b>				<b>50.00</b>		
003	201.0450	<b>REMOVE AND STOCKPILE ON SITE GRANITE CURB</b>	<b>LF</b>			
		BRIDGE NO 583				
		PROVIDENCE PLACE		17.00	0014	01
<b>Item 201.0450 Total:</b>				<b>17.00</b>		
004	201.0610	<b>REMOVE AND DISPOSE DIRECTIONAL, WARNING, REGULATORY, SERVICE, AND STREET SIGNS</b>	<b>EACH</b>			
		BRIDGE NO 583				
		PROVIDENCE PLACE		2.00	0014	01
<b>Item 201.0610 Total:</b>				<b>2.00</b>		
005	201.0617	<b>REMOVE AND DISPOSE CONDUIT - ALL SIZES</b>	<b>LF</b>			
		BRIDGE NO 583				
		PROMENADE & PROVIDENCE PLACE		100.00	0014	01
<b>Item 201.0617 Total:</b>				<b>100.00</b>		
006	202.0100	<b>EARTH EXCAVATION</b>	<b>CY</b>			
		BRIDGE NO 583				

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
006	202.0100	Cont.				
		PROMENADE STREET - ROADWAY		10.00	0014	01
		PROMENADE STREET - SIDEWALK		10.00	0014	01
		PROVIDENCE PLACE - ROADWAY		10.00	0014	01
		PROVIDENCE PLACE - SIDEWALK		10.00	0014	01
<b>Item 202.0100 Total:</b>				<b>40.00</b>		
007	203.0100	<b>STRUCTURAL EXCAVATION EARTH</b>	<b>CY</b>			
		BRIDGE NO 583				
		PIER 5		46.00	0014	01
		PIER 6		17.00	0014	01
<b>Item 203.0100 Total:</b>				<b>63.00</b>		
008	203.0700	<b>PERVIOUS FILL</b>	<b>CY</b>			
		BRIDGE NO 583				
		PROMENADE STREET		10.00	0014	01
		PROVIDENCE PLACE		50.00	0014	01
<b>Item 203.0700 Total:</b>				<b>60.00</b>		
009	204.0100	<b>TRIMMING AND FINE GRADING</b>	<b>SY</b>			
		BRIDGE NO 583				
		PROMENADE STREET - ROADWAY		20.00	0014	01
		PROMENADE STREET - SIDEWALK		20.00	0014	01
		PROVIDENCE PLACE - ROADWAY		30.00	0014	01
		PROVIDENCE PLACE - SIDEWALK		30.00	0014	01
<b>Item 204.0100 Total:</b>				<b>100.00</b>		
010	207.0206	<b>SAND BAG EROSION DIKE STANDARD</b>	<b>PBAG</b>			
		<b>9.6.0</b>				
		BRIDGE NO 583				
		NEAR PIER 5 SHORING TOWER		502.00	0014	01
		NEAR PIER 6 SHORING		333.00	0014	01
<b>Item 207.0206 Total:</b>				<b>835.00</b>		

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
011	209.9901	<b>INLET PROTECTION</b>	<b>EACH</b>			
		BRIDGE NO 583				
		PROMENADE STREET - EAST		2.00	0014	01
		PROVIDENCE PLACE - WEST		1.00	0014	01
<b>Item 209.9901 Total:</b>				<b>3.00</b>		
012	212.2000	<b>CLEANING AND MAINTENANCE OF EROSION CONTROLS</b>	<b>LS</b>			
		PROJECT WIDE				
		PROJECT WIDE		1.00	0014	01
<b>Item 212.2000 Total:</b>				<b>1.00</b>		
013	301.0300	<b>CRUSHED STONE OR CRUSHED GRAVEL BASE MODIFIED</b>	<b>CY</b>			
		BRIDGE NO 583				
		PROMENADE STREET - BETWEEN RAIL & WALL AREA		2.00	0014	01
		PROMENADE STREET - SIDEWALK		3.00	0014	01
<b>Item 301.0300 Total:</b>				<b>5.00</b>		
014	302.0100	<b>GRAVEL BORROW SUBBASE COURSE</b>	<b>CY</b>			
		BRIDGE NO 583				
		PROMENADE STREET - ROADWAY		7.00	0014	01
		PROMENADE STREET - SIDEWALK		4.00	0014	01
		PROVIDENCE PLACE - ROADWAY		8.00	0014	01
		PROVIDENCE PLACE - SIDEWALK		6.00	0014	01
<b>Item 302.0100 Total:</b>				<b>25.00</b>		
015	401.1000	<b>CLASS 19.0 HMA</b>	<b>TON</b>			
		BRIDGE NO 583				
		PROMENADE STREET		5.00	0014	01
		PROVIDENCE PLACE		5.00	0014	01
<b>Item 401.1000 Total:</b>				<b>10.00</b>		

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
016	401.2000	<b>CLASS 12.5 HMA</b>	<b>TON</b>			
		BRIDGE NO 583				
		PROMENADE STREET		2.00	0014	01
		PROVIDENCE PLACE		3.00	0014	01
<b>Item 401.2000 Total:</b>				<b>5.00</b>		
017	403.0300	<b>ASPHALT EMULSION TACK COAT</b>	<b>SY</b>			
		BRIDGE NO 583				
		PROMENADE STREET		165.00	0014	01
		PROVIDENCE PLACE		195.00	0014	01
<b>Item 403.0300 Total:</b>				<b>360.00</b>		
018	708.9040	<b>CLEANING AND FLUSHING PIPE ALL SIZES</b>	<b>LF</b>			
		BRIDGE NO 583				
		PROMENADE STREET - CB TO CB		15.00	0014	01
		PROMENADE STREET - CB TO MH		27.00	0014	01
		PROMENADE STREET - MH TO RIVER		18.00	0014	01
		PROVIDENCE PLACE - CB TO RIVER		20.00	0014	01
<b>Item 708.9040 Total:</b>				<b>80.00</b>		
019	708.9041	<b>CLEANING CATCH BASINS ALL TYPES AND SIZES</b>	<b>EACH</b>			
		BRIDGE NO 583				
		PROMENADE STREET		2.00	0014	01
		PROVIDENCE PLACE		1.00	0014	01
<b>Item 708.9041 Total:</b>				<b>3.00</b>		
020	803.0300	<b>PARTIAL REMOVAL AND DISPOSAL OF EXISTING CONCRETE MASONRY</b>	<b>CY</b>			

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
020	803.0300	Cont.				
		BRIDGE NO 579				
		PIER 3, EAST CANTILEVER		7.00	0014	01
		PIER 6, FULL PIER		64.00	0014	01
		BRIDGE NO 583				
		WALL NEAR PIER 5		15.00	0014	01
<b>Item 803.0300 Total:</b>				<b>86.00</b>		
021	808.0505	CONCRETE SUBSTRUCTURE CLASS HP	CY			
		3/4'' WALL STEMS				
		BRIDGE 583				
		RETAINING WALLS AT PROMENADE		21.00	0014	01
		AND PROV PLACE				
<b>Item 808.0505 Total:</b>				<b>21.00</b>		
022	808.0601	CONCRETE SUBSTRUCTURE CLASS HP	CY			
		3/4'' PIERS, COL, CAP				
		BRIDGE NO 579				
		PIER 3, EAST CANTILEVER		7.00	0014	01
		PIER 6, FULL PIER		64.00	0014	01
<b>Item 808.0601 Total:</b>				<b>71.00</b>		
023	808.9901	FIBER WRAP BRIDGE 577 PIER 1 FOR	SF			
		STRENGTHENING				
		BRIDGE NO 577				
		PIER 1		184.00	0014	01
<b>Item 808.9901 Total:</b>				<b>184.00</b>		
024	808.9902	FIBER WRAP BRIDGE 577 PIER 1 FOR	SF			
		PROTECTION				
		BRIDGE NO 577				
		PIER 1		249.00	0014	01
<b>Item 808.9902 Total:</b>				<b>249.00</b>		



### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
025	810.0210	<b>GALVANIZED BAR REINFORCEMENT GRADE</b>	<b>LBS</b>			
		60				
		BRIDGE NO 579				
		PIER 3		1,497.00	0014	01
		PIER 6		21,200.00	0014	01
		WALL		4,539.00	0014	01
<b>Item 810.0210 Total:</b>				<b>27,236.00</b>		
026	817.2100	<b>REPAIRS TO STRUCTURAL CONCRETE</b>	<b>CF</b>			
		<b>MASONRY (PNEUMATIC MORTAR)</b>				
		PROJECT WIDE				
		PROJECT WIDE		73.00	0014	01
<b>Item 817.2100 Total:</b>				<b>73.00</b>		
027	817.2110	<b>REPAIRS TO STRUCTURAL CONCRETE</b>	<b>CF</b>			
		<b>MASONRY (PATCHING MORTAR)</b>				
		PROJECT WIDE				
		PROJECT WIDE		17.00	0014	01
<b>Item 817.2110 Total:</b>				<b>17.00</b>		
028	817.2140	<b>REPAIRS TO STRUCTURAL CONCRETE</b>	<b>CF</b>			
		<b>MASONRY FORM AND CAST IN PLACE</b>				
		PROJECT WIDE				
		PROJECT WIDE		639.00	0014	01
<b>Item 817.2140 Total:</b>				<b>639.00</b>		
029	819.0800	<b>DRILL AND GROUT REINFORCING DOWELS</b>	<b>EACH</b>			
		BRIDGE NO 579				
		PIER 3, EAST CANTILEVER		18.00	0014	01
		PIER 6, EAST COLUMN		64.00	0014	01
<b>Item 819.0800 Total:</b>				<b>82.00</b>		
030	819.9901	<b>ADHESIVE ANCHOR FOR DOWEL BARS</b>	<b>EACH</b>			

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
030	819.9901	Cont. (1-1/4")				
		BRIDGE NO 579				
		PIER 6		64.00	0014	01
<b>Item 819.9901 Total:</b>				<b>64.00</b>		
031	820.0110	CONCRETE SURFACE TREATMENT (PROTECTIVE COATING)	SF			
		BRIDGE NO 579				
		PIER 3		69.00	0014	01
		PIER 6		196.00	0014	01
<b>Item 820.0110 Total:</b>				<b>265.00</b>		
032	824.9901	TEMPORARY JACKING AND SHORING OF BEAMS BRIDGE 579 PIER 3	LS			
		BRIDGE NO 579				
		PIER 3		1.00	0014	01
<b>Item 824.9901 Total:</b>				<b>1.00</b>		
033	824.9902	TEMPORARY JACKING AND SHORING OF BEAMS BRIDGE 579 PIER 6	LS			
		BRIDGE 579				
		PIER 6		1.00	0014	01
<b>Item 824.9902 Total:</b>				<b>1.00</b>		
034	824.9903	TEMPORARY JACKING AND SHORING OF BEAMS BRIDGE 583 PIER 5	LS			
		BRIDGE 583				
		PIER 5		1.00	0014	01
<b>Item 824.9903 Total:</b>				<b>1.00</b>		
035	824.9904	TEMPORARY JACKING AND SHORING OF BEAMS BRIDGE 583 PIER 6	ACRE			
		BRIDGE NO 583				

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
035	824.9904 Cont.	PIER 6		1.00	0014	01
<b>Item 824.9904 Total:</b>				<b>1.00</b>		
036	828.9901	<b>REMOVE STOCKPILE AND REINSTALL 4 BAR RAIL</b>	<b>LF</b>			
		PROJECT WIDE				
		PROMENADE		22.00	0014	01
		PROVIDENCE PLACE		48.00	0014	01
<b>Item 828.9901 Total:</b>				<b>70.00</b>		
037	836.0100	<b>STRUCTURAL CONCRETE CRACK REPAIR BY EPOXY-RESIN BASE ADHESIVE INJECTION</b>	<b>LF</b>			
		PROJECT WIDE				
		BRIDGE NO 579		8.00	0014	01
		BRIDGE NO 583		20.00	0014	01
<b>Item 836.0100 Total:</b>				<b>28.00</b>		
038	903.0410	<b>TEMPORARY CHAIN LINK FENCE</b>	<b>LF</b>			
		BRIDGE NO 577				
		UNDER BRIDGE NO 577		198.00	0014	01
		BRIDGE NO 583				
		PHASE 1		100.00	0014	01
		PHASE 2		90.00	0014	01
<b>Item 903.0410 Total:</b>				<b>388.00</b>		
039	903.0411	<b>TEMPORARY CHAIN LINK GATE</b>	<b>EACH</b>			
		BRIDGE NO 577				
		UNDER BRIDGE NO 577		1.00	0014	01
		BRIDGE NO 583				
		PHASE 1		1.00	0014	01
		PHASE 2		1.00	0014	01
<b>Item 903.0411 Total:</b>				<b>3.00</b>		

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
040	904.0101	REMOVE AND RESET FENCE AND/OR RAILING CHAIN LINK BRIDGE NO 577 UNDER BRIDGE NO 577	LF			
				195.00	0014	01
<b>Item 904.0101 Total:</b>				<b>195.00</b>		
041	905.0110	PORTLAND CEMENT SIDEWALK MONOLITHIC STANDARD 43.1.0 BRIDGE NO 583 PROVIDENCE PLACE - SIDEWALK PROVIDENCE PLACE - WCR	CY			
				4.00	0014	01
				9.00	0014	01
<b>Item 905.0110 Total:</b>				<b>13.00</b>		
042	906.0112	GRANITE CURB PROVIDENCE STANDARD 7" STRAIGHT BRIDGE NO 583 PROVIDENCE PLACE	LF			
				3.00	0014	01
<b>Item 906.0112 Total:</b>				<b>3.00</b>		
043	906.0700	REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT, CIRCULAR ALL TYPES BRIDGE NO 583 PROMENADE STREET PROVIDENCE PLACE	LF			
				22.00	0014	01
				19.00	0014	01
<b>Item 906.0700 Total:</b>				<b>41.00</b>		
044	906.9901	6'-0" GRANITE TRANSITION CURB STANDARD 7.3.2 MODIFIED, 7" WIDTH BRIDGE NO 583 PROVIDENCE PLACE	EACH			
				1.00	0014	01
<b>Item 906.9901 Total:</b>				<b>1.00</b>		

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
045	906.9902	GRANITE WHEELCHAIR RAMP TRANSITION CURB MODIFIED, 7" WIDTH BRIDGE NO 583 PROVIDENCE PLACE	EACH	1.00	0014	01
Item 906.9902 Total:				1.00		
046	906.9903	GRANITE RAMP STONE STRAIGHT STANDARD 7.3.9 MODIFIED, 7" WIDTH BRIDGE NO 583 PROVIDENCE PLACE	EACH	1.00	0014	01
Item 906.9903 Total:				1.00		
047	914.5010	FLAGPERSONS PROJECT WIDE AS NEEDED	MHRS	960.00	0014	01
Item 914.5010 Total:				960.00		
048	914.5020	FLAGPERSONS - OVERTIME PROJECT WIDE AS NEEDED	MHRS	96.00	0014	01
Item 914.5020 Total:				96.00		
049	916.9901	NARROW CONDITION IMPACT ATTENUATOR FOR TRAFFIC CONTROL PROJECT WIDE AS NEEDED	EACH	2.00	0014	01
Item 916.9901 Total:				2.00		
050	920.0055	PLACED STONE RIPRAP R-3, R-4, R-5 STANDARD 8.3.0 BRIDGE NO 583 NEAR PIER 5	SY	20.00	0014	01

**Distribution of Quantities**

Project Name - Repairs to Bridge Piers for Bridges #579 &amp; #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
050	920.0055	Cont.				
				<b>Item 920.0055 Total:</b>	<b>20.00</b>	
051	922.0100	<b>TEMPORARY CONSTRUCTION SIGNS</b>	<b>SF</b>			
<b>STANDARD 29.1.0 AND 27.1.1</b>						
PROJECT WIDE						
		AS NEEDED		46.00	0014	01
		E5-2A (36"x48")		12.00	0014	01
		G20-2 (36"x18")		9.00	0014	01
		G20-2 (48"x24")		8.00	0014	01
		R.I. STANDARD 27.1.1 (24"x36")		12.00	0014	01
		R.I. STANDARD 27.1.1 (48"x72")		24.00	0014	01
		R11-2(MOD) (30"x48")		10.00	0014	01
		R1-2 (36"x36"x36")		8.00	0014	01
		R9-11R (24"x18")		3.00	0014	01
		R9-9 (24"x12")		2.00	0014	01
		R9-9(MOD) (24"x18")		3.00	0014	01
		W1-4B (36"x36")		9.00	0014	01
		W16-7P (12"X24")		2.00	0014	01
		W20-1 (36"x36")		36.00	0014	01
		W20-1 (48"x48")		16.00	0014	01
		W20-5(MOD) (36"x36")		9.00	0014	01
		W20-5AR (48"x48")		32.00	0014	01
		W20-5R (48"x48")		32.00	0014	01
		W3-2 (36"x36")		9.00	0014	01
		W5-1 (36"x36")		9.00	0014	01
		W9-2(MOD) (36"x36")		9.00	0014	01
				<b>Item 922.0100 Total:</b>	<b>300.00</b>	
052	923.0105	<b>DRUM BARRICADE STANDARD 26.2.0</b>	<b>BDAY</b>			
PROJECT WIDE						
		AS NEEDED		2,300.00	0014	01

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
052	923.0105	Cont.		2,300.00		
Item 923.0105 Total:						
053	923.0120	PLASTIC PIPE BARRICADE STANDARD	EACH			
		26.3.0				
		PROJECT WIDE				
		AS NEEDED		3.00	0014	01
Item 923.0120 Total:				3.00		
054	923.0200	FLUORESCENT TRAFFIC CONES STANDARD	EACH			
		26.1.0				
		PROJECT WIDE				
		AS NEEDED		25.00	0014	01
Item 923.0200 Total:				25.00		
055	926.0110	ANCHORED SINGLE-FACE PRECAST	LF			
		CONCRETE BARRIER FOR TEMPORARY				
		TRAFFIC CONTROL				
		BRIDGE NO 583				
		PHASE 1		160.00	0014	01
		PHASE 2		110.00	0014	01
Item 926.0110 Total:				270.00		
056	928.9901	SHADOW OR ADVANCED WARNING VEHICLE	HRS			
		WITH IMPACT ATTENUATOR AND				
		FLASHING ARROW BOARD OR CHANGEABLE				
		MESSAGE SIGN				
		PROJECT WIDE				
		AS NEEDED		720.00	0014	01
Item 928.9901 Total:				720.00		
057	929.0110	FIELD OFFICE	PMO			
		PROJECT WIDE				
		PROJECT WIDE		14.00	0014	01

**Distribution of Quantities**

Project Name - Repairs to Bridge Piers for Bridges #579 &amp; #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
057	929.0110	Cont.				
		Item 929.0110 Total:		14.00		
058	932.0210	FULL DEPTH SAWCUT OF BITUMINOUS PAVEMENT AND RIGID BASE BRIDGE NO 583	LF			
		PROMENADE STREET		37.00	0014	01
		PROVIDENCE PLACE		48.00	0014	01
		Item 932.0210 Total:		85.00		
059	932.0230	FULL DEPTH SAWCUT OF PORTLAND CEMENT CONCRETE SIDEWALK/DRIVEWAY BRIDGE NO 583	LF			
		PROVIDENCE PLACE - SIDEWALK		12.00	0014	01
		Item 932.0230 Total:		12.00		
060	936.0110	MOBILIZATION PROJECT WIDE	LS			
		PROJECT WIDE		1.00	0014	01
		Item 936.0110 Total:		1.00		
061	937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION PROJECT WIDE	LS			
		PROJECT WIDE		1.00	0014	01
		Item 937.0200 Total:		1.00		
062	942.0200	DETECTABLE WARNING PANEL STANDARD 48.1.0 BRIDGE NO 583	SF			
		PROVIDENCE PLACE - SIDEWALKS		12.00	0014	01
		Item 942.0200 Total:		12.00		
063	T04.6902	'2' STRANDED COPPER CONDUCTOR 600V	LF			



### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
063	T04.6902	Cont. INSULATION				
		BRIDGE NO 583				
		PROMENADE		140.00	0014	01
		PROVIDENCE PLACE		140.00	0014	01
<b>Item T04.6902 Total:</b>				<b>280.00</b>		
064	T04.6906	'6' STRANDED COPPER CONDUCTOR 600V LF INSULATION				
		BRIDGE NO 583				
		PROMENADE		60.00	0014	01
		PROVIDENCE PLACE		60.00	0014	01
<b>Item T04.6906 Total:</b>				<b>120.00</b>		
065	T04.6910	'10' STRANDED COPPER CONDUCTOR 600V INSULATION	LF			
		BRIDGE NO 583				
		PROMENADE		90.00	0014	01
		PROVIDENCE PLACE		90.00	0014	01
<b>Item T04.6910 Total:</b>				<b>180.00</b>		
066	T04.7300	IN-LINE FUSED DISCONNECT DEVICE WITH FUSE WEATHERPROOF	EACH			
		BRIDGE NO 583				
		PROMENADE		4.00	0014	01
		PROVIDENCE PLACE		4.00	0014	01
<b>Item T04.7300 Total:</b>				<b>8.00</b>		
067	T04.7400	IN-LINE UNFUSED DISCONNECT DEVICE	EACH			
		BRIDGE NO 583				
		PROMENADE		4.00	0014	01
		PROVIDENCE PLACE		4.00	0014	01
<b>Item T04.7400 Total:</b>				<b>8.00</b>		

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
068	T04.7500	<b>SPLICE KIT</b>	<b>EACH</b>			
		BRIDGE NO 583				
		PROMENADE		2.00	0014	01
		PROVIDENCE PLACE		2.00	0014	01
<b>Item T04.7500 Total:</b>				<b>4.00</b>		
069	T05.0100	<b>PRECAST TYPE A HANDHOLE STANDARD</b>	<b>EACH</b>			
		<b>18.2.0</b>				
		BRIDGE NO 583				
		PROMENADE		1.00	0014	01
		PROVIDENCE PLACE		2.00	0014	01
<b>Item T05.0100 Total:</b>				<b>3.00</b>		
070	T05.1030	<b>ADJUST HANDHOLE TO GRADE</b>	<b>EACH</b>			
		BRIDGE NO 583				
		PROVIDENCE PLACE		1.00	0014	01
<b>Item T05.1030 Total:</b>				<b>1.00</b>		
071	T06.5130	<b>3 INCH SCHEDULE 40 POLYVINYL</b>	<b>LF</b>			
		<b>CHLORIDE PLASTIC CONDUIT -</b>				
		<b>UNDERGROUND</b>				
		BRIDGE NO 583				
		PROMENADE		60.00	0014	01
		PROVIDENCE PLACE		60.00	0014	01
<b>Item T06.5130 Total:</b>				<b>120.00</b>		
072	T08.1700	<b>REMOVE AND RELOCATE LIGHT STANDARD</b>	<b>EACH</b>			
		BRIDGE NO 583				
		PROMENADE		2.00	0014	01
		PROVIDENCE PLACE		2.00	0014	01
<b>Item T08.1700 Total:</b>				<b>4.00</b>		
073	T08.9901	<b>LIGHT STANDARD FOUNDATION WITH</b>	<b>EACH</b>			

**Distribution of Quantities**

Project Name - Repairs to Bridge Piers for Bridges #579 &amp; #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
073	T08.9901	Cont. ANCHOR BOLTS STANDARD 18.1.0				
		BRIDGE NO 583				
		PROMENADE & PROVIDENCE PLACE		2.00	0014	01
				<b>Item T08.9901 Total:</b>	<b>2.00</b>	
074	T08.9902	ORNAMENTAL POLE/LUMINAIRE - REMOVAL, TEMPORARY INSTALLATION PERMANENT & RE-INSTALLATION	EACH			
		BRIDGE NO 583				
		PROMENADE & PROVIDENCE PLACE		2.00	0014	01
				<b>Item T08.9902 Total:</b>	<b>2.00</b>	
075	T15.0100	DIRECTIONAL REGULATORY AND WARNING SIGNS	SF			
		PROVIDENCE PLACE				
		W11-2L (36"X36") X 2 SIGNS		18.00	0014	01
		W11-2R (36"X36") X 2 SIGNS		18.00	0014	01
		W16-7PL (24"X12")		2.00	0014	01
		W16-7PR (24"X12")		2.00	0014	01
		W16-9P (24"X12") X 2 SIGNS		4.00	0014	01
				<b>Item T15.0100 Total:</b>	<b>44.00</b>	
076	T20.1000	REMOVE EXISTING PAVEMENT MARKINGS	LF			
		BRIDGE NO 583				
		PHASE 1		775.00	0014	01
		PHASE 1 REMOVAL		1,105.00	0014	01
		PHASE 2		90.00	0014	01
				<b>Item T20.1000 Total:</b>	<b>1,970.00</b>	
077	T20.1010	REMOVE EXISTING PAVEMENT MARKINGS	EACH			
		BRIDGE NO 583				
		PHASE 1		2.00	0014	01
		PHASE 2 REMOVAL		1.00	0014	01

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
077	T20.1010	Cont.		3.00		
Item T20.1010 Total:				3.00		
078	T20.2004	4 INCH EPOXY RESIN PAVEMENT	LF			
		MARKINGS WHITE				
		BRIDGE NO 583				
		PHASE 1		425.00	0014	01
		PHASE 2		60.00	0014	01
Item T20.2004 Total:				485.00		
079	T20.2012	12 INCH EPOXY RESIN PAVEMENT	LF			
		MARKINGS WHITE				
		BRIDGE NO 583				
		PHASE 2		20.00	0014	01
		PROVIDENCE PLACE		130.00	0014	01
Item T20.2012 Total:				150.00		
080	T20.2014	4 INCH EPOXY RESIN PAVEMENT	LF			
		MARKINGS YELLOW				
		BRIDGE NO 583				
		PHASE 1		50.00	0014	01
		PHASE 2		30.00	0014	01
		PROMENADE STREET		60.00	0014	01
		PROVIDENCE PLACE		60.00	0014	01
Item T20.2014 Total:				200.00		
081	T20.2020	EPOXY RESIN PAVEMENT ARROW -	EACH			
		STRAIGHT, LEFT, RIGHT, OR COMBINED				
		STANDARD 20.1.0				
		BRIDGE NO 583				
		PHASE 1		1.00	0014	01
Item T20.2020 Total:				1.00		
082	T20.2022	EPOXY RESIN PAVEMENT MARKING WORD	EACH			

### Distribution of Quantities

Project Name - Repairs to Bridge Piers for Bridges #579 & #583

Estimate Name - Advertising

R.I. Contract No. - 2018-CB-109

FAP Nos: 405-421-891

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
082	T20.2022	Cont. "ONLY" STANDARD 20.1.0				
		BRIDGE NO 583				
		PHASE 1		1.00	0014	01
<b>Item T20.2022 Total:</b>				<b>1.00</b>		
083	T20.2204	4 INCH TEMPORARY EPOXY RESIN PAVEMENT MARKINGS WHITE	LF			
		BRIDGE NO 583				
		PHASE 1		765.00	0014	01
<b>Item T20.2204 Total:</b>				<b>765.00</b>		
084	T20.2234	TEMPORARY EPOXY RESIN PAVEMENT MARKING - YIELD LINE SYMBOL	EACH			
		BRIDGE NO 583				
		PHASE 2		1.00	0014	01
<b>Item T20.2234 Total:</b>				<b>1.00</b>		
085	T20.2304	4 INCH TEMPORARY EPOXY RESIN PAVEMENT MARKINGS YELLOW	LF			
		BRIDGE NO 583				
		PHASE 1		340.00	0014	01
<b>Item T20.2304 Total:</b>				<b>340.00</b>		