

DISTRIBUTION OF QUANTITIES

Table of Contents - Distribution of Quantities

Project Name - Immediate Needs Steel Repairs Contract 2

Estimate Name - Advertise

R.I. Contract No. - 2019-CB-012

FAP Nos: 405-421-946

ItemCode	Description	Page
803.9901	CLEANING BRIDGE BEAM SEATS	1
824.9901	STEEL REPAIRS	1
825.9901	PAINTING STRUCTURAL STEEL	1
914.5010	FLAGPERSONS	1
914.5020	FLAGPERSONS - OVERTIME	2
922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	2
923.0105	DRUM BARRICADE STANDARD 26.2.0	3
923.0120	PLASTIC PIPE BARRICADE STANDARD 26.3.0	3
923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	4
924.0113	ADVANCE WARNING ARROW PANEL	4
925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	4
928.9901	TRUCK MOUNTED ATTENUATOR WITH TRUCK MOUNTED FLASHING ARROW BOARD	4
929.0110	FIELD OFFICE	5
936.0100	MOBILIZATION AND DEMOBILIZATION	5
937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	5

Distribution of Quantities

Project Name - Immediate Needs Steel Repairs Contract 2

Estimate Name - Advertise

R.I. Contract No. - 2019-CB-012

FAP Nos: 405-421-946

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
001	803.9901	CLEANING BRIDGE BEAM SEATS	EACH			
		BEAM SEATS				
		BRIDGE NO. 623		1.00	0014	01
		BRIDGE NO. 672		1.00	0014	01
		BRIDGE NO. 855		1.00	0014	01
		BRIDGE NO. 905		1.00	0014	01
		BRIDGE NO. 908		1.00	0014	01
Item 803.9901 Total:				5.00		
002	824.9901	STEEL REPAIRS	LBS			
		STEEL REPAIRS				
		AS DIRECTED BY THE ENGINEER		2,900.00	0014	01
		BRIDGE NO. 623		7,700.00	0014	01
		BRIDGE NO. 672		9,000.00	0014	01
		BRIDGE NO. 855		4,800.00	0014	01
		BRIDGE NO. 905		3,500.00	0014	01
		BRIDGE NO. 908		1,100.00	0014	01
Item 824.9901 Total:				29,000.00		
003	825.9901	PAINTING STRUCTURAL STEEL	SF			
		PAINTING STRUCTURAL STEEL				
		AS DIRECTED BY THE ENGINEER		2,000.00	0014	01
		BRIDGE NO. 623		1,700.00	0014	01
		BRIDGE NO. 672		1,900.00	0014	01
		BRIDGE NO. 855		1,700.00	0014	01
		BRIDGE NO. 905		500.00	0014	01
		BRIDGE NO. 908		700.00	0014	01
Item 825.9901 Total:				8,500.00		
004	914.5010	FLAGPERSONS	MHRS			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		120.00	0014	01
		BRIDGE NO. 623		80.00	0014	01

Distribution of Quantities

Project Name - Immediate Needs Steel Repairs Contract 2

Estimate Name - Advertise

R.I. Contract No. - 2019-CB-012

FAP Nos: 405-421-946

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
004	914.5010	Cont.				
		BRIDGE NO. 672		40.00	0014	01
		BRIDGE NO. 855		240.00	0014	01
		BRIDGE NO. 905		160.00	0014	01
Item 914.5010 Total:				640.00		
005	914.5020	FLAGPERSONS - OVERTIME	MHRS			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		125.00	0014	01
		(~25%)				
Item 914.5020 Total:				125.00		
006	922.0100	TEMPORARY CONSTRUCTION SIGNS	SF			
		STANDARD 29.1.0 AND 27.1.1				
		BRIDGE NO. 623				
		RI STD 27.1.1 24X36		12.00	0014	01
		W20-1 36X36		18.00	0014	01
		W20-1 48X48		16.00	0014	01
		W20-4 36X36		18.00	0014	01
		W20-7 36X36		18.00	0014	01
		W24-1L 36X36		9.00	0014	01
		W24-1R 36X36		9.00	0014	01
		BRIDGE NO. 672				
		ASDIRECTED BY THE ENGINEER		41.00	0014	01
		RI STD 24.1.1 (24X36)		24.00	0014	01
		W20-1 (24X36)		36.00	0014	01
		W20-4 (24X36)		36.00	0014	01
		W20-7 (24X36)		36.00	0014	01
		W21-5A (36X36)		9.00	0014	01
		W24-1L (36X36)		9.00	0014	01
		W24-1R (36X36)		9.00	0014	01
		BRIDGE NO. 855				
		RI STD 27.1.1 24X36		12.00	0014	01
		W20-1 36X36		18.00	0014	01

Distribution of Quantities

Project Name - Immediate Needs Steel Repairs Contract 2

Estimate Name - Advertise

R.I. Contract No. - 2019-CB-012

FAP Nos: 405-421-946

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
006	922.0100	Cont.				
		W20-1 48X48		16.00	0014	01
		W20-4 36X36		18.00	0014	01
		W20-7 36X36		18.00	0014	01
		W24-1L 36X36		9.00	0014	01
		W24-1R 36X36		9.00	0014	01
		BRIDGE NO. 905				
		G20-2 48X24		8.00	0014	01
		W13-1P 24X24		4.00	0014	01
		W13-4P 24X24		4.00	0014	01
		W20-1A 48X48		16.00	0014	01
		W5-1 48X48		16.00	0014	01
		W5-4 48X48		16.00	0014	01
		BRIDGE NO. 908				
		W20-1 36X36		27.00	0014	01
		W20-1 48X48		16.00	0014	01
		W20-5R 36X36		9.00	0014	01
		W4-2R 36X36		18.00	0014	01
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		166.00	0014	01
Item 922.0100 Total:				700.00		
007	923.0105	DRUM BARRICADE STANDARD 26.2.0	BDAY			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		100.00	0014	01
		BRIDGE NO. 623		200.00	0014	01
		BRIDGE NO. 672		50.00	0014	01
		BRIDGE NO. 855		600.00	0014	01
		BRIDGE NO. 905		200.00	0014	01
		BRIDGE NO. 908		600.00	0014	01
Item 923.0105 Total:				1,750.00		
008	923.0120	PLASTIC PIPE BARRICADE STANDARD	EACH			
		26.3.0				

Distribution of Quantities

Project Name - Immediate Needs Steel Repairs Contract 2

Estimate Name - Advertise

R.I. Contract No. - 2019-CB-012

FAP Nos: 405-421-946

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
008	923.0120	Cont. PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		5.00	0014	01
Item 923.0120 Total:				5.00		
009	923.0200	FLUORESCENT TRAFFIC CONES STANDARD	EACH			
		26.1.0				
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		75.00	0014	01
		BRIDGE NO. 623		25.00	0014	01
		BRIDGE NO. 672		50.00	0014	01
		BRIDGE NO. 855		25.00	0014	01
		BRIDGE NO. 905		25.00	0014	01
		BRIDGE NO. 908		50.00	0014	01
Item 923.0200 Total:				250.00		
010	924.0113	ADVANCE WARNING ARROW PANEL	PDAY			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		40.00	0014	01
		BRIDGE NO. 908		60.00	0014	01
Item 924.0113 Total:				100.00		
011	925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	PDAY			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		100.00	0014	01
Item 925.0112 Total:				100.00		
012	928.9901	TRUCK MOUNTED ATTENUATOR WITH	HRS			
		TRUCK MOUNTED FLASHING ARROW BOARD				
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		40.00	0014	01
		BRIDGE NO. 672		40.00	0014	01
		BRIDGE NO. 905		160.00	0014	01
Item 928.9901 Total:				240.00		

Distribution of Quantities

Project Name - Immediate Needs Steel Repairs Contract 2

Estimate Name - Advertise

R.I. Contract No. - 2019-CB-012

FAP Nos: 405-421-946

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
013	929.0110	FIELD OFFICE	PMO			
		AS DIRECTED BY THE ENGINEER				
		AS DIRECTED BY THE ENGINEER		6.00	0014	01
Item 929.0110 Total:				6.00		
014	936.0100	MOBILIZATION AND DEMOBILIZATION	LS			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		1.00	0014	01
Item 936.0100 Total:				1.00		
015	937.0200	MAINTENANCE AND MOVEMENT TRAFFIC	LS			
		PROTECTION				
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		1.00	0014	01
Item 937.0200 Total:				1.00		