

DISTRIBUTION OF QUANTITIES

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR

Estimate Name - BRIDGE 327 PS&E

R.I. Contract No. - 2021-CB-012

FAP Nos: BRO-0327(005)

ItemCode	Description	Page
201.0321	CLEARING AND GRUBBING	1
201.0401	REMOVE AND DISPOSE GRANITE CURB	1
201.0403	REMOVE AND DISPOSE SIDEWALKS	1
201.0409	REMOVE AND DISPOSE FLEXIBLE PAVEMENT	1
201.0419	REMOVE AND DISPOSE FENCE	1
201.0614	REMOVE AND STOCKPILE HANDHOLES - TYPE A	1
202.0100	EARTH EXCAVATION	1
202.0600	LOAM EXCAVATION	2
202.9912	LOAD, HAUL, MANAGE AND DISPOSE CONTAMINATED SOIL, ALL TYPES	2
203.0100	STRUCTURAL EXCAVATION EARTH	2
203.0400	STRUCTURAL EXCAVATION UNCLASSIFIED	2
203.0650	CRUSHED STONE FILL UNDER STRUCTURES	2
204.0100	TRIMMING AND FINE GRADING	2
206.0312	COMPOST FILTER SOCK 12 INCH DIAMETER	3
206.9901	CATCH BASIN INLET CONTROL	3
211.0100	CONSTRUCTION ACCESSES STANDARD 9.9.0	3
212.2100	MAINTENANCE AND CLEANING OF EROSION AND POLLUTION CONTROLS	3
213.0100	PLACEMENT OF MILLINGS BENEATH GUARDRAIL	3
302.0100	GRAVEL BORROW SUBBASE COURSE	3
401.1000	CLASS 19.0 HMA	4
401.3100	MODIFIED CLASS 9.5 HMA	4
403.0300	ASPHALT EMULSION TACK COAT	4
501.0103	PORTLAND CEMENT CONCRETE BASE	4
707.0950	ADJUST TELEPHONE MANHOLE TO GRADE	4
707.0955	ADJUST ELECTRICAL MANHOLE TO GRADE	4
707.1100	ADJUST CATCH BASINS	5
707.1900	ADJUST FRAME & COVER TO GRADE	5
708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	5
712.9901	INSTALLATION OF GAS MAIN	5
713.8269	ADJUST WATER GATE BOXES TO GRADE	5
713.8300	ADJUST GAS GATE BOXES TO GRADE	5
800.9901	RESERVOIR AVENUE BRIDGE NO. 327 REHABILITATION	5
803.9902	REMOVE AND DISPOSE EXISTING BRIDGE SIDEWALK SUPERSTRUCTURE	6
	RESERVOIR AVENUE BRIDGE NO. 327	
803.9904	REMOVE AND DISPOSE EXISTING BRIDGE SUBSTRUCTURE RESERVOIR AVENUE BRIDGE NO. 327	6
817.2112	REPAIRS TO STRUCTURE CONCRETE MASONRY - PATCHING MORTAR	6
817.2142	REPAIRS TO STRUCTURE CONCRETE MASONRY - FORM AND CAST IN PLACE CONCRETE	6
820.0300	HIGH PRESSURE WATER CLEANING OF BRIDGE STRUCTURES	6
836.9901	BRIDGE NO. 327 STRUCTURAL CONCRETE CRACK REPAIR	7
901.0160	REFLECTORIZED TRIANGULAR DELINEATORS STANDARD 34.2.5	7
901.0175	STEEL THRIE BEAM GUARDRAIL SINGLE FACE STANDARD 34.5.3	7
901.0178	STEEL THRIE BEAM GUARDRAIL TERMINAL END SECTION	7
901.0185	STEEL THRIE BEAM BRIDGE CONNECTION	7
901.9901	STEEL THRIE BEAM GUARDRAIL SINGLE FACE BENT RADIUS	8
901.9902	THRIE BEAM SINGLE FACE SPECIAL	8
903.0206	CHAIN LINK FENCE 6' STD 31.2.0	8
903.0410	TEMPORARY CHAIN LINK FENCE	8
905.0110	PORTLAND CEMENT SIDEWALK MONOLITHIC STANDARD 43.1.0	8
906.0110	GRANITE CURB, QUARRY SPLIT STRAIGHT, STANDARD 7.3.0	8
906.0111	GRANITE CURB, QUARRY SPLIT CIRCULAR, STANDARD 7.3.0	9

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR

Estimate Name - BRIDGE 327 PS&E

R.I. Contract No. - 2021-CB-012

FAP Nos: BRO-0327(005)

ItemCode	Description	Page
906.0120	GRANITE WHEELCHAIR RAMP CURB STANDARDS 7.3.3, 43.3.0 AND 43.3.1	9
906.0130	GRANITE RAMP STONE STRAIGHT STANDARD 7.3.9	9
906.0131	GRANITE RAMP STONE CIRCULAR STANDARD 7.3.9	9
906.9901	3'-0" GRANITE TRANSITION CURB AT BRIDGE	9
907.0100	WATER FOR DUST CONTROL	9
914.5010	FLAGPERSONS	10
914.5020	FLAGPERSONS - OVERTIME	10
922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	10
923.0105	DRUM BARRICADE STANDARD 26.2.0	10
923.0125	PLASTIC PIPE TYPE III BARRICADE STANDARD 26.3.1	10
923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	10
926.9901	UNANCHORED BARRIER FOR TEMPORARY TRAFFIC CONTROL (MASH TL-3)	11
926.9902	TEMPORARY IMPACT ATTENUATOR	11
929.0110	FIELD OFFICE	11
931.0110	CLEANING AND SWEEPING PAVEMENT	11
932.0200	FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT	11
932.0230	FULL DEPTH SAWCUT OF PORTLAND CEMENT CONCRETE SIDEWALK/DRIVEWAY	11
935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING	12
936.0110	MOBILIZATION	12
936.9901	FORCE ACCOUNT BANK - UNEXPECTED AMTRAK DOWN TIME	12
937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	12
942.0200	DETECTABLE WARNING PANEL STANDARD 48.1.0	12
943.0200	TRAINEE MAN-HOURS	12
L01.0104	PLANTABLE SOIL 4 INCHES DEEP	13
L02.0101	GENERAL HIGHWAY SEEDING (TYPE 1)	13
L11.0102	TREE PLANT PROTECTION DEVICE STANDARD 51.1.0	13
T01.9901	ELECTRIC MANHOLE 6506	13
T01.9905	ELECTRIC 2-5" BRIDGE MOUNTED FIBERGLASS	13
T01.9906	ELECTRIC MANHOLE 6507	13
T04.5002	6 AWG 2 CONDUCTOR CABLE 600V INSULATION	14
T04.5302	14 AWG 2 CONDUCTOR TWISTED SHIELDED CABLE	14
T04.5303	14 AWG 3 CONDUCTOR CABLE	14
T04.5305	14 AWG 5 CONDUCTOR CABLE	14
T04.5307	14 AWG 7 CONDUCTOR CABLE	14
T04.9901	6 PAIR NO. 19 AWG COMMUNICATION CABLE, 300V INSULATION (IMSA 39-2 OR 40-2)	14
T05.0100	PRECAST TYPE A HANDHOLE STANDARD 18.2.0	15
T05.0400	BREAK INTO EXISTING HANDHOLE	15
T05.1030	ADJUST HANDHOLE TO GRADE	15
T06.1020	2 IN. RIGID STEEL CONDUIT - UNDERGROUND	15
T06.2020	2 IN. RIGID STEEL CONDUIT-OVERHEAD	15
T06.3030	3 IN. RIGID STEEL CONDUIT-UNDER EXISTING PAVEMENT	15
T06.6020	2 INCH POLYVINYL CHLORIDE PLASTIC CONDUIT-OVERHEAD	16
T06.9901	ELECTRIC 2-5" PVC CONDUIT	16
T06.9908	4" RISER	16
T06.9910	COMMUNICATION 1-4" PVC CONDUIT	16
T06.9911	COMMUNICATIONS 2-4" PVC CONDUIT	16
T11.2008	TRAFFIC SIGNAL STANDARD, 8 FOOT, STD 19.4.0 ALUMINUM PEDESTAL POLE AND FOUNDATION	16
T11.9999	TEMPORARY TRAFFIC SIGNAL SYSTEMS - CONSTRUCTION AND MAINTENANCE	17

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR

Estimate Name - BRIDGE 327 PS&E

R.I. Contract No. - 2021-CB-012

FAP Nos: BRO-0327(005)

ItemCode	Description	Page
T12.9901	VIDEO DETECTION SYSTEM	17
T13.1000	TRAFFIC DETECTORS-LOOP, STANDARD 19.6.0	17
T13.8210	ACCESSIBLE PEDESTRIAN DETECTOR - PUSHBUTTON WITH SIGN	17
T14.9902	1 WAY 2 SECTION PEDESTAL MOUNTED LED PEDESTRIAN SIGNAL HEAD 12 INCH W/ COUNTDOWN TIMER	17
T15.0100	DIRECTIONAL REGULATORY AND WARNING SIGNS	18
T15.0200	REMOVE AND RELOCATE DIRECTIONAL REGULATORY AND WARNING SIGN	18
T20.0706	6 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS	18
T20.0712	12 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS	18
T20.0904	4 INCH YELLOW WATERBORNE PAINT PAVEMENT MARKINGS	18
T20.0906	6 INCH YELLOW WATERBORNE PAINT PAVEMENT MARKINGS	18
T20.2406	6 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS	19
T20.2412	12 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS	19
T20.2804	4 INCH YELLOW FINAL EPOXY RESIN PAVEMENT MARKINGS	19
T20.2808	8 INCH YELLOW FINAL EPOXY RESIN PAVEMENT MARKINGS	19
T20.3401	FINAL EPOXY RESIN PAVEMENT MARKING SYMBOL - ARROW (STRAIGHT, LEFT, RIGHT OR COMBINED) STANDARD 20.1.0	19
T20.3410	FINAL EPOXY RESIN PAVEMENT MARKING WORD ("ONLY", "STOP", "YIELD", "AHEAD", "XING", "SCHOOL", OR OTHER) STANDARD 20.1.0	20
T20.4506	REMOVE PAVEMENT MARKING LINE - LESS THAN OR EQUAL TO 6 INCHES WIDE	20
T20.4511	REMOVE PAVEMENT MARKING SYMBOL - ARROW (STRAIGHT, LEFT, RIGHT OR COMBINED)	20

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
001	201.0321	CLEARING AND GRUBBING	SY			
		BR 327				
		RESERVOIR AVE		410.00	0011	01
Item 201.0321 Total:				410.00		
002	201.0401	REMOVE AND DISPOSE GRANITE CURB	LF			
		BR 327				
		RESERVOIR AVE		550.00	0011	01
Item 201.0401 Total:				550.00		
003	201.0403	REMOVE AND DISPOSE SIDEWALKS	SY			
		BR 327				
		RESERVOIR AVE		500.00	0011	01
Item 201.0403 Total:				500.00		
004	201.0409	REMOVE AND DISPOSE FLEXIBLE PAVEMENT	SY			
		BR 327				
		RESERVOIR		3,650.00	0011	01
Item 201.0409 Total:				3,650.00		
005	201.0419	REMOVE AND DISPOSE FENCE	LF			
		BR 327				
		RESERVOIR AVE		110.00	0011	01
Item 201.0419 Total:				110.00		
006	201.0614	REMOVE AND STOCKPILE HANDHOLES - TYPE A	EACH			
		BR 327				
		RESERVOIR AVE		7.00	0011	01
Item 201.0614 Total:				7.00		
007	202.0100	EARTH EXCAVATION	CY			

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
007	202.0100	Cont. BR 327				
		RESERVOIR AVE		2,500.00	0011	01
				Item 202.0100 Total:	2,500.00	
008	202.0600	LOAM EXCAVATION	CY			
		BR 327				
		RESERVOIR AVE		50.00	0011	01
				Item 202.0600 Total:	50.00	
009	202.9912	LOAD, HAUL, MANAGE AND DISPOSE	CY			
		CONTAMINATED SOIL, ALL TYPES				
		BR 327				
		RESERVOIR AVE/BRIDGE		365.00	0011	01
		RESERVOIR AVE/HIGHWAY		2,900.00	0011	01
				Item 202.9912 Total:	3,265.00	
010	203.0100	STRUCTURAL EXCAVATION EARTH	CY			
		BR 327				
		RESERVOIR AVE		365.00	0011	01
				Item 203.0100 Total:	365.00	
011	203.0400	STRUCTURAL EXCAVATION UNCLASSIFIED	CY			
		BR 327				
		RESERVOIR AVE		19.00	0011	01
				Item 203.0400 Total:	19.00	
012	203.0650	CRUSHED STONE FILL UNDER STRUCTURES	CY			
		BR 327				
		RESERVOIR AVE		237.00	0011	01
				Item 203.0650 Total:	237.00	
013	204.0100	TRIMMING AND FINE GRADING	SY			
		BR 327				

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
013	204.0100	Cont. RESERVOIR AVE		30.00	0011	01
Item 204.0100 Total:				30.00		
014	206.0312	COMPOST FILTER SOCK 12 INCH DIAMETER BR 327 RESERVOIR AVENUE	LF	1,190.00	0011	01
Item 206.0312 Total:				1,190.00		
015	206.9901	CATCH BASIN INLET CONTROL BR 327 RESERVOIR AVE	EACH	10.00	0011	01
Item 206.9901 Total:				10.00		
016	211.0100	CONSTRUCTION ACCESSES STANDARD 9.9.0 BR 327 RESERVOIR AVE	SY	150.00	0011	01
Item 211.0100 Total:				150.00		
017	212.2100	MAINTENANCE AND CLEANING OF EROSION AND POLLUTION CONTROLS BR 327 RESERVOIR AVE	LS	1.00	0011	01
Item 212.2100 Total:				1.00		
018	213.0100	PLACEMENT OF MILLINGS BENEATH GUARDRAIL BR 327 RESERVOIR AVENUE	LF	180.00	0011	01
Item 213.0100 Total:				180.00		
019	302.0100	GRAVEL BORROW SUBBASE COURSE	CY			

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
019	302.0100	Cont. BR 327				
		RESERVOIR AVE		1,250.00	0011	01
				Item 302.0100 Total:	1,250.00	
020	401.1000	CLASS 19.0 HMA	TON			
		BR 327				
		RESERVOIR AVE		2,160.00	0011	01
				Item 401.1000 Total:	2,160.00	
021	401.3100	MODIFIED CLASS 9.5 HMA	TON			
		BR 327				
		RESERVOIR AVE		370.00	0011	01
				Item 401.3100 Total:	370.00	
022	403.0300	ASPHALT EMULSION TACK COAT	SY			
		BR 327				
		RESERVOIR AVE		4,400.00	0011	01
				Item 403.0300 Total:	4,400.00	
023	501.0103	PORTLAND CEMENT CONCRETE BASE	SY			
		BR 327				
		RESERVOIR AVE		550.00	0011	01
				Item 501.0103 Total:	550.00	
024	707.0950	ADJUST TELEPHONE MANHOLE TO GRADE	EACH			
		BR 327				
		RESERVOIR AVENUE		1.00	0011	01
				Item 707.0950 Total:	1.00	
025	707.0955	ADJUST ELECTRICAL MANHOLE TO GRADE	EACH			
		BR 327				
		RESERVOIR AVENUE		3.00	0011	01
				Item 707.0955 Total:	3.00	

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
026	707.1100	ADJUST CATCH BASINS	EACH			
		BR 327				
		RESERVOIR AVENUE		1.00	0011	01
Item 707.1100 Total:				1.00		
027	707.1900	ADJUST FRAME & COVER TO GRADE	EACH			
		BR 327				
		RESERVOIR AVENUE		10.00	0011	01
Item 707.1900 Total:				10.00		
028	708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	EACH			
		BR 327				
		RESERVOIR AVE		10.00	0011	01
Item 708.9041 Total:				10.00		
029	712.9901	INSTALLATION OF GAS MAIN	LS			
		BR 327				
		RESERVOIR AVENUE		1.00	0011	01
Item 712.9901 Total:				1.00		
030	713.8269	ADJUST WATER GATE BOXES TO GRADE	EACH			
		BR 327				
		RESERVOIR AVE		10.00	0011	01
Item 713.8269 Total:				10.00		
031	713.8300	ADJUST GAS GATE BOXES TO GRADE	EACH			
		BR 327				
		RESERVOIR AVE		2.00	0011	01
Item 713.8300 Total:				2.00		
032	800.9901	RESERVOIR AVENUE BRIDGE NO. 327 REHABILITATION	LS			

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
032	800.9901 Cont.	RESERVOIR AVENUE				
		BR 327		1.00	0011	01
Item 800.9901 Total:				1.00		
033	803.9902	REMOVE AND DISPOSE EXISTING BRIDGE SIDEWALK SUPERSTRUCTURE RESERVOIR AVENUE BRIDGE NO. 327	LS			
		BR 327				
		RESERVOIR AVE		1.00	0011	01
Item 803.9902 Total:				1.00		
034	803.9904	REMOVE AND DISPOSE EXISTING BRIDGE SUBSTRUCTURE RESERVOIR AVENUE BRIDGE NO. 327	LS			
		BR327 RESERVOIR AVENUE				
		BR 327		1.00	0011	01
Item 803.9904 Total:				1.00		
035	817.2112	REPAIRS TO STRUCTURE CONCRETE MASONRY - PATCHING MORTAR	CF			
		BR 327				
		RESERVOIR AVE		30.00	0011	01
Item 817.2112 Total:				30.00		
036	817.2142	REPAIRS TO STRUCTURE CONCRETE MASONRY - FORM AND CAST IN PLACE CONCRETE	CF			
		BR 327				
		RESERVOIR AVENUE		30.00	0011	01
Item 817.2142 Total:				30.00		
037	820.0300	HIGH PRESSURE WATER CLEANING OF BRIDGE STRUCTURES	EACH			

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
037	820.0300 Cont.	BR 327				
		RESERVOIR AVENUE		1.00	0011	01
Item 820.0300 Total:				1.00		
038	836.9901	BRIDGE NO. 327 STRUCTURAL CONCRETE	LF			
		CRACK REPAIR				
		BR 327				
		RESERVOIR AVE		150.00	0011	01
Item 836.9901 Total:				150.00		
039	901.0160	REFLECTORIZED TRIANGULAR	EACH			
		DELINEATORS STANDARD 34.2.5				
		BR 327				
		RESERVOIR AVE		30.00	0011	01
Item 901.0160 Total:				30.00		
040	901.0175	STEEL THRIE BEAM GUARDRAIL SINGLE	LF			
		FACE STANDARD 34.5.3				
		BR327 RESERVOIR AVENUE				
		BR327		135.00	0011	01
Item 901.0175 Total:				135.00		
041	901.0178	STEEL THRIE BEAM GUARDRAIL	EACH			
		TERMINAL END SECTION				
		BR327 RESERVOIR AVENUE				
		BR327		4.00	0011	01
Item 901.0178 Total:				4.00		
042	901.0185	STEEL THRIE BEAM BRIDGE CONNECTION	EACH			
		BR 327				
		RESERVOIR AVE		4.00	0011	01
Item 901.0185 Total:				4.00		

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
043	901.9901	STEEL THRIE BEAM GUARDRAIL SINGLE	LF			
		FACE BENT RADIUS				
		BR 327 RESERVOIR AVENUE				
		BR 327		30.00	0011	01
		Item 901.9901 Total:		30.00		
044	901.9902	THRIE BEAM SINGLE FACE SPECIAL	LF			
		BR327 RESERVOIR AVENUE				
		BR327		50.00	0011	01
		Item 901.9902 Total:		50.00		
045	903.0206	CHAIN LINK FENCE 6' STD 31.2.0	LF			
		BR 327				
		RESERVOIR AVENUE		60.00	0011	01
		Item 903.0206 Total:		60.00		
046	903.0410	TEMPORARY CHAIN LINK FENCE	LF			
		BR 327				
		RESERVOIR AVE		800.00	0011	01
		Item 903.0410 Total:		800.00		
047	905.0110	PORTLAND CEMENT SIDEWALK	CY			
		MONOLITHIC STANDARD 43.1.0				
		BR 327				
		RESERVOIR AVE		55.00	0011	01
		Item 905.0110 Total:		55.00		
048	906.0110	GRANITE CURB, QUARRY SPLIT	LF			
		STRAIGHT, STANDARD 7.3.0				
		BR 327				
		RESERVOIR AVE		380.00	0011	01
		Item 906.0110 Total:		380.00		

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
049	906.0111	GRANITE CURB, QUARRY SPLIT CIRCULAR, STANDARD 7.3.0 BR 327 RESERVOIR AVE	LF	150.00	0011	01
Item 906.0111 Total:				150.00		
050	906.0120	GRANITE WHEELCHAIR RAMP CURB STANDARDS 7.3.3, 43.3.0 AND 43.3.1 BR 327 RESERVOIR AVE	EACH	25.00	0011	01
Item 906.0120 Total:				25.00		
051	906.0130	GRANITE RAMP STONE STRAIGHT STANDARD 7.3.9 BR 327 RESERVOIR AVE	EACH	5.00	0011	01
Item 906.0130 Total:				5.00		
052	906.0131	GRANITE RAMP STONE CIRCULAR STANDARD 7.3.9 BR 327 RESERVOIR AVE	EACH	4.00	0011	01
Item 906.0131 Total:				4.00		
053	906.9901	3'-0" GRANITE TRANSITION CURB AT BRIDGE BR 327 RESERVOIR AVENUE BR 327	EACH	4.00	0011	01
Item 906.9901 Total:				4.00		
054	907.0100	WATER FOR DUST CONTROL BR 327 RESERVOIR AVE	MGAL	6.00	0011	01

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
054	907.0100	Cont.				
		Item 907.0100 Total:		6.00		
055	914.5010	FLAGPERSONS	MHRS			
		BR 327				
		RESERVOIR AVE		4,700.00	0011	01
		Item 914.5010 Total:		4,700.00		
056	914.5020	FLAGPERSONS - OVERTIME	MHRS			
		BR 327				
		RESERVOIR AVE		1,000.00	0011	01
		Item 914.5020 Total:		1,000.00		
057	922.0100	TEMPORARY CONSTRUCTION SIGNS	SF			
		STANDARD 29.1.0 AND 27.1.1				
		BR 327				
		RESERVOIR AVE		700.00	0011	01
		Item 922.0100 Total:		700.00		
058	923.0105	DRUM BARRICADE STANDARD 26.2.0	BDAY			
		BR 327				
		RESERVOIR AVE		16,800.00	0011	01
		Item 923.0105 Total:		16,800.00		
059	923.0125	PLASTIC PIPE TYPE III BARRICADE	EACH			
		STANDARD 26.3.1				
		BR 327				
		RESERVOIR AVE		30.00	0011	01
		Item 923.0125 Total:		30.00		
060	923.0200	FLUORESCENT TRAFFIC CONES STANDARD	EACH			
		26.1.0				
		BR 327				
		RESERVOIR AVE		40.00	0011	01

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
060	923.0200	Cont.				
				Item 923.0200 Total:		
				40.00		
061	926.9901	UNANCHORED BARRIER FOR TEMPORARY TRAFFIC CONTROL (MASH TL-3)	LF			
		BR 327				
		RESERVOIR AVENUE		280.00	0011	01
		RESERVOIR AVENUE/TRAFFIC		350.00	0011	01
				Item 926.9901 Total:		
				630.00		
062	926.9902	TEMPORARY IMPACT ATTENUATOR	EACH			
		BR 327				
		RESERVOIR AVE		3.00	0011	01
				Item 926.9902 Total:		
				3.00		
063	929.0110	FIELD OFFICE	PMO			
		BR 327				
		RESERVOIR AVE		12.00	0011	01
				Item 929.0110 Total:		
				12.00		
064	931.0110	CLEANING AND SWEEPING PAVEMENT	HSY			
		BR 327				
		RESERVOIR AVE		45.00	0011	01
				Item 931.0110 Total:		
				45.00		
065	932.0200	FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT	LF			
		BR 327				
		RESERVOIR AVE		700.00	0011	01
				Item 932.0200 Total:		
				700.00		
066	932.0230	FULL DEPTH SAWCUT OF PORTLAND CEMENT CONCRETE SIDEWALK/DRIVEWAY	LF			
		BR 327				

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
066	932.0230	Cont. RESERVOIR AVE		100.00	0011	01
Item 932.0230 Total:				100.00		
067	935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING BR 327 RESERVOIR AVE	SY	700.00	0011	01
Item 935.0400 Total:				700.00		
068	936.0110	MOBILIZATION BR 327 RESERVOIR AVE	LS	1.00	0011	01
Item 936.0110 Total:				1.00		
069	936.9901	FORCE ACCOUNT BANK - UNEXPECTED AMTRAK DOWN TIME BR327 RESERVOIR AVENUE BR 327	EACH	1.00	0011	01
Item 936.9901 Total:				1.00		
070	937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION BR 327 RESERVOIR AVE	LS	1.00	0011	01
Item 937.0200 Total:				1.00		
071	942.0200	DETECTABLE WARNING PANEL STANDARD 48.1.0 BR 327 RESERVOIR AVE	SF	96.00	0011	01
Item 942.0200 Total:				96.00		
072	943.0200	TRAINEE MAN-HOURS	MHRS			

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
072	943.0200 Cont.	BR 327				
		RESERVOIR AVENUE		1,300.00	0011	01
				Item 943.0200 Total:	1,300.00	
073	L01.0104	PLANTABLE SOIL 4 INCHES DEEP	SY			
		BR 327				
		RESERVOIR AVE		4,410.00	0011	01
				Item L01.0104 Total:	4,410.00	
074	L02.0101	GENERAL HIGHWAY SEEDING (TYPE 1)	SY			
		BR 327				
		RESERVOIR AVE		4,410.00	0011	01
				Item L02.0101 Total:	4,410.00	
075	L11.0102	TREE PLANT PROTECTION DEVICE	EACH			
		STANDARD 51.1.0				
		BR 327				
		RESERVOIR AVE		8.00	0011	01
				Item L11.0102 Total:	8.00	
076	T01.9901	ELECTRIC MANHOLE 6506	EACH			
		BR 327				
		RESERVOIR AVENUE		1.00	0011	01
				Item T01.9901 Total:	1.00	
077	T01.9905	ELECTRIC 2-5" BRIDGE MOUNTED	LF			
		FIBERGLASS				
		BR 327				
		RESERVOIR AVENUE		175.00	0011	01
				Item T01.9905 Total:	175.00	
078	T01.9906	ELECTRIC MANHOLE 6507	EACH			
		BR 327				

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
078	T01.9906	Cont. RESERVOIR AVENUE		1.00	0011	01
Item T01.9906 Total:				1.00		
079	T04.5002	6 AWG 2 CONDUCTOR CABLE 600V INSULATION BR 327 RESERVOIR AVE	LF	1,220.00	0011	01
Item T04.5002 Total:				1,220.00		
080	T04.5302	14 AWG 2 CONDUCTOR TWISTED SHIELDED CABLE BR 327 RESERVOIR AVE	LF	650.00	0011	01
Item T04.5302 Total:				650.00		
081	T04.5303	14 AWG 3 CONDUCTOR CABLE BR 327 RESERVOIR AVE	LF	800.00	0011	01
Item T04.5303 Total:				800.00		
082	T04.5305	14 AWG 5 CONDUCTOR CABLE BR 327 RESERVOIR AVE	LF	2,350.00	0011	01
Item T04.5305 Total:				2,350.00		
083	T04.5307	14 AWG 7 CONDUCTOR CABLE BR 327 RESERVOIR AVE	LF	980.00	0011	01
Item T04.5307 Total:				980.00		
084	T04.9901	6 PAIR NO. 19 AWG COMMUNICATION CABLE, 300V INSULATION (IMSA 39-2 OR 40-2)	LF			

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
084	T04.9901 Cont.	BR 327				
		RESERVOIR AVE		720.00	0011	01
				Item T04.9901 Total:	720.00	
085	T05.0100	PRECAST TYPE A HANDHOLE STANDARD	EACH			
		18.2.0				
		BR 327				
		RESERVOIR AVE		7.00	0011	01
				Item T05.0100 Total:	7.00	
086	T05.0400	BREAK INTO EXISTING HANDHOLE	EACH			
		BR 327				
		RESERVOIR AVE		7.00	0011	01
				Item T05.0400 Total:	7.00	
087	T05.1030	ADJUST HANDHOLE TO GRADE	EACH			
		BR 327				
		RESERVOIR AVE		4.00	0011	01
				Item T05.1030 Total:	4.00	
088	T06.1020	2 IN. RIGID STEEL CONDUIT -	LF			
		UNDERGROUND				
		BR 327				
		RESERVOIR AVE		5.00	0011	01
				Item T06.1020 Total:	5.00	
089	T06.2020	2 IN. RIGID STEEL CONDUIT-OVERHEAD	LF			
		BR 327				
		RESERVOIR AVE		40.00	0011	01
				Item T06.2020 Total:	40.00	
090	T06.3030	3 IN. RIGID STEEL CONDUIT-UNDER	LF			
		EXISTING PAVEMENT				

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
090	T06.3030 Cont.	BR 327				
		RESERVOIR AVENUE/TRAFFIC		480.00	0011	01
				Item T06.3030 Total:	480.00	
091	T06.6020	2 INCH POLYVINYL CHLORIDE PLASTIC	LF			
		CONDUIT-OVERHEAD				
		BR 327				
		RESERVOIR AVE		20.00	0011	01
				Item T06.6020 Total:	20.00	
092	T06.9901	ELECTRIC 2-5" PVC CONDUIT	LF			
		BR 327				
		RESERVOIR AVENUE		325.00	0011	01
				Item T06.9901 Total:	325.00	
093	T06.9908	4" RISER	LF			
		BR 327				
		RESERVOIR AVENUE		40.00	0011	01
				Item T06.9908 Total:	40.00	
094	T06.9910	COMMUNICATION 1-4" PVC CONDUIT	LF			
		BR 327				
		RESERVOIR AVE		530.00	0011	01
				Item T06.9910 Total:	530.00	
095	T06.9911	COMMUNICATIONS 2-4" PVC CONDUIT	LF			
		BR 327				
		RESERVOIR AVENUE		110.00	0011	01
				Item T06.9911 Total:	110.00	
096	T11.2008	TRAFFIC SIGNAL STANDARD, 8 FOOT, STD	EACH			
		19.4.0 ALUMINUM PEDESTAL POLE AND				
		FOUNDATION				

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
096	T11.2008 Cont.	BR 327				
		RESERVOIR AVE		2.00	0011	01
Item T11.2008 Total:				2.00		
097	T11.9999	TEMPORARY TRAFFIC SIGNAL SYSTEMS - LS				
		CONSTRUCTION AND MAINTENANCE				
		BR 327				
		RESERVOIR AVE		1.00	0011	01
Item T11.9999 Total:				1.00		
098	T12.9901	VIDEO DETECTION SYSTEM	EACH			
		BR 327				
		RESERVOIR AVE		3.00	0011	01
Item T12.9901 Total:				3.00		
099	T13.1000	TRAFFIC DETECTORS-LOOP, STANDARD	LF			
		19.6.0				
		BR 327				
		RESERVOIR AVE		560.00	0011	01
Item T13.1000 Total:				560.00		
100	T13.8210	ACCESSIBLE PEDESTRIAN DETECTOR -	EACH			
		PUSHBUTTON WITH SIGN				
		BR 327				
		RESERVOIR AVE		2.00	0011	01
Item T13.8210 Total:				2.00		
101	T14.9902	1 WAY 2 SECTION PEDESTAL MOUNTED	EACH			
		LED PEDESTRIAN SIGNAL HEAD 12 INCH				
		W/ COUNTDOWN TIMER				
		BR 327				
		RESERVOIR AVE		2.00	0011	01
Item T14.9902 Total:				2.00		

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
102	T15.0100	DIRECTIONAL REGULATORY AND WARNING SIGNS	SF			
		BR 327				
		RESERVOIR AVENUE		2.00	0011	01
Item T15.0100 Total:				2.00		
103	T15.0200	REMOVE AND RELOCATE DIRECTIONAL REGULATORY AND WARNING SIGN	EACH			
		BR 327				
		RESERVOIR AVENEUE		1.00	0011	01
Item T15.0200 Total:				1.00		
104	T20.0706	6 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS	LF			
		BR 327				
		RESERVOIR AVE		3,500.00	0011	01
Item T20.0706 Total:				3,500.00		
105	T20.0712	12 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS	LF			
		BR 327				
		RESERVOIR AVE		80.00	0011	01
Item T20.0712 Total:				80.00		
106	T20.0904	4 INCH YELLOW WATERBORNE PAINT PAVEMENT MARKINGS	LF			
		BR 327				
		RESERVOIR AVE		1,400.00	0011	01
Item T20.0904 Total:				1,400.00		
107	T20.0906	6 INCH YELLOW WATERBORNE PAINT PAVEMENT MARKINGS	LF			
		BR 327				

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
107	T20.0906 Cont.	RESERVOIR AVE		1,400.00	0011	01
Item T20.0906 Total:				1,400.00		
108	T20.2406	6 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS BR 327 RESERVOIR AVE	LF	1,900.00	0011	01
Item T20.2406 Total:				1,900.00		
109	T20.2412	12 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS BR 327 RESERVOIR AVE	LF	1,100.00	0011	01
Item T20.2412 Total:				1,100.00		
110	T20.2804	4 INCH YELLOW FINAL EPOXY RESIN PAVEMENT MARKINGS BR 327 RESERVOIR AVE	LF	1,050.00	0011	01
Item T20.2804 Total:				1,050.00		
111	T20.2808	8 INCH YELLOW FINAL EPOXY RESIN PAVEMENT MARKINGS BR 327 RESERVOIR AVENUE	LF	351.00	0011	01
Item T20.2808 Total:				351.00		
112	T20.3401	FINAL EPOXY RESIN PAVEMENT MARKING SYMBOL - ARROW (STRAIGHT, LEFT, RIGHT OR COMBINED) STANDARD 20.1.0 BR 327 RESERVOIR AVE	EACH	5.00	0011	01

Item T20.3401 Total:

5.00

Distribution of Quantities

Project Name - Bridge Group 59C - Reservoir Ave RR
 Estimate Name - BRIDGE 327 PS&E
 R.I. Contract No. - 2021-CB-012
 FAP Nos: BRO-0327(005)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
113	T20.3410	FINAL EPOXY RESIN PAVEMENT MARKING WORD ("ONLY", "STOP", "YIELD", "AHEAD", "XING", "SCHOOL", OR OTHER) STANDARD 20.1.0 BR 327 RESERVOIR AVENUE	EACH	5.00	0011	01
Item T20.3410 Total:				5.00		
114	T20.4506	REMOVE PAVEMENT MARKING LINE - LESS THAN OR EQUAL TO 6 INCHES WIDE BR 327 RESERVOIR AVENUE	LF	8,300.00	0011	01
Item T20.4506 Total:				8,300.00		
115	T20.4511	REMOVE PAVEMENT MARKING SYMBOL - ARROW (STRAIGHT, LEFT, RIGHT OR COMBINED) BR 327 RESERVOIR AVENUE	EACH	4.00	0011	01
Item T20.4511 Total:				4.00		