

DISTRIBUTION OF QUANTITIES

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| ItemCode | Description | Page |
|-----------------|---|-------------|
| 201.0321 | CLEARING AND GRUBBING | 1 |
| 201.0401 | REMOVE AND DISPOSE GRANITE CURB | 1 |
| 201.0409 | REMOVE AND DISPOSE FLEXIBLE PAVEMENT | 1 |
| 201.0415 | REMOVE AND DISPOSE GUARDRAIL AND POST ALL TYPES | 1 |
| 201.0421 | REMOVE AND DISPOSE BITUMINOUS CURB | 2 |
| 201.0428 | REMOVE AND DISPOSE FRAME AND GRATE OR FRAME AND COVER | 2 |
| 201.0610 | REMOVE AND DISPOSE DIRECTIONAL, WARNING, REGULATORY, SERVICE, AND STREET SIGNS | 2 |
| 201.9901 | REMOVE AND STOCKPILE TEMPORARY CONCRETE BARRIER | 2 |
| 201.9902 | REMOVE AND STOCKPILE SHOCK ABSORBING BARRIER MODULES | 2 |
| 201.9903 | REMOVE AND STOCKPILE POLYTHYLENE DRUM BARRICADES | 3 |
| 201.9904 | REMOVE AND STOCKPILE TYPE 3 BARRICADES | 3 |
| 201.9905 | REMOVE AND STOCKPILE SIGNS | 3 |
| 202.0100 | EARTH EXCAVATION | 3 |
| 202.0800 | GRAVEL BORROW | 4 |
| 203.0100 | STRUCTURAL EXCAVATION EARTH | 4 |
| 203.0650 | CRUSHED STONE FILL UNDER STRUCTURES | 4 |
| 203.0700 | PERVIOUS FILL | 4 |
| 204.0100 | TRIMMING AND FINE GRADING | 4 |
| 206.0312 | COMPOST FILTER SOCK 12 INCH DIAMETER | 5 |
| 209.0200 | SACK INSERT CATCH BASIN INLET PROTECTION | 5 |
| 209.9901 | SEDIMENTATION CONTROL CURB INLET STRUCTURES | 6 |
| 212.2100 | MAINTENANCE AND CLEANING OF EROSION AND POLLUTION CONTROLS | 6 |
| 213.0100 | PLACEMENT OF MILLINGS BENEATH GUARDRAIL | 6 |
| 301.9901 | PEASTONE | 6 |
| 301.9902 | GRS REINFORCED BACKFILL | 7 |
| 302.0100 | GRAVEL BORROW SUBBASE COURSE | 7 |
| 401.1000 | CLASS 19.0 HMA | 7 |
| 401.3101 | MODIFIED CLASS 9.5 HMA FOR BRIDGE DECKS | 8 |
| 403.0300 | ASPHALT EMULSION TACK COAT | 8 |
| 410.1000 | TEMPORARY PATCHING MATERIAL/TRENCHES | 9 |
| 601.0200 | CLASS XX PORTLAND CEMENT CONCRETE | 9 |
| 603.1000 | CONTROLLED LOW STRENGTH MATERIAL | 9 |
| 701.0412 | REINFORCED CONCRETE PIPE M 170 CLASS III 12 INCH | 9 |
| 702.0516 | FRAME AND GRATE, HIGH CAPACITY, STANDARD 6.3.4 | 10 |
| 702.0522 | FRAME AND COVER STANDARD 6.2.1 | 10 |
| 702.0543 | GRANITE APRON STONE 38'' STANDARD 7.3.8 | 10 |
| 702.0840 | ALTERNATE TOP COVER ROUND PRECAST MANHOLES AND CATCH BASINS STANDARD 4.7.2 | 10 |
| 702.9901 | MODIFIED PRECAST 4'-0" ROUND CATCH BASIN WITH 4'-0" DEEP SUMP STD 4.4.0M | 10 |
| 702.9902 | PERMEABLE PAVER SAND FILTER SYSTEM | 11 |
| 707.1200 | ADJUST CATCH BASIN TO MANHOLE | 11 |
| 708.9040 | CLEANING AND FLUSHING PIPE ALL SIZES | 11 |
| 708.9041 | CLEANING CATCH BASINS ALL TYPES AND SIZES | 11 |
| 708.9042 | CLEANING MANHOLES ALL TYPES AND SIZES | 12 |
| 800.9901 | HUNTS MILLS BRIDGE NO. 208 | 12 |
| 803.9901 | REMOVE AND DISPOSE EXISTING HUNTS MILLS BRIDGE NO. 208 | 12 |
| 804.9901 | DRILLED MICROPILES | 12 |
| 808.0321 | CONCRETE SUBSTRUCTURE CLASS HP 3/4'' WALL CAP | 12 |
| 810.0702 | WELDED WIRE FABRIC (GALVANIZED) | 13 |
| 817.9901 | REMOVE, SALVAGE AND DELIVER IDENTIFICATION TILES | 13 |
| 819.0800 | DRILL AND GROUT REINFORCING DOWELS | 13 |

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
Estimate Name - Bridge Group 69E - Hunts Mills
R.I. Contract No. - 2021-CB-063
FAP Nos: BRO-0208(004)

| ItemCode | Description | Page |
|-----------------|--|-------------|
| 901.0101 | GUARDRAIL STEEL BEAM SINGLE FACE EARTH AND ASPHALT | 13 |
| 901.9901 | GUARDRAIL CONNECTION TO END POST APPROACH SECTION WITH NESTED RAIL | 13 |
| 901.9902 | GUARDRAIL CONNECTION TO END POST TRAILING END SECTION WITHOUT NESTED RAIL | 13 |
| 901.9903 | GUARDRAIL END TREATMENT MASH COMPLIANT TEST LEVEL 3 | 14 |
| 903.0410 | TEMPORARY CHAIN LINK FENCE | 14 |
| 906.0110 | GRANITE CURB, QUARRY SPLIT STRAIGHT, STANDARD 7.3.0 | 14 |
| 906.0111 | GRANITE CURB, QUARRY SPLIT CIRCULAR, STANDARD 7.3.0 | 14 |
| 906.0118 | 6' GRANITE TRANSITION CURB, QUARRY SPLIT SPECIAL TRANSITION STANDARD 7.3.2 | 15 |
| 906.0210 | CEMENT CONCRETE CURB PRECAST STRAIGHT STANDARD 7.1.0 | 15 |
| 906.9901 | CONCRETE BLOCK PAVERS | 15 |
| 907.0100 | WATER FOR DUST CONTROL | 15 |
| 914.5010 | FLAGPERSONS | 15 |
| 914.5020 | FLAGPERSONS - OVERTIME | 16 |
| 916.0600 | SHOCK ABSORBING BARRIER MODULES | 16 |
| 919.0101 | TEST PITS | 16 |
| 920.0040 | DUMPED STONE RIPRAP R-3, R-4, R-5 STANDARD 8.3.0 | 16 |
| 920.0135 | BEDDING FOR RIPRAP FS-2 STANDARD 8.3.0 | 16 |
| 920.0200 | FILTER FABRIC FOR RIP-RAP | 16 |
| 922.0100 | TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1 | 17 |
| 923.0105 | DRUM BARRICADE STANDARD 26.2.0 | 18 |
| 923.0120 | PLASTIC PIPE BARRICADE STANDARD 26.3.0 | 18 |
| 923.0200 | FLUORESCENT TRAFFIC CONES STANDARD 26.1.0 | 18 |
| 925.0112 | PORTABLE CHANGEABLE MESSAGE SIGN | 19 |
| 926.0140 | REFLECTIVE DELINEATORS FOR TEMPORARY CONCRETE BARRIERS | 19 |
| 926.9901 | UNANCORED BARRIER FOR TEMPORARY TRAFFIC CONTROL TEST LEVEL 3 | 19 |
| 929.0110 | FIELD OFFICE | 19 |
| 931.0110 | CLEANING AND SWEEPING PAVEMENT | 19 |
| 932.0100 | CUTTING AND MATCHING ASPHALT | 19 |
| 932.0200 | FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT | 20 |
| 935.0400 | REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING | 20 |
| 936.0100 | MOBILIZATION AND DEMOBILIZATION | 20 |
| 937.0200 | MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION | 20 |
| 943.0200 | TRAINEE MAN-HOURS | 21 |
| L01.0102 | LOAM BORROW 4 INCHES DEEP | 21 |
| L02.0102 | RESIDENTIAL SEEDING (TYPE 2) | 21 |
| L08.0109 | TREE TRIMMING | 21 |
| L09.9901 | SELECTIVE CLEARING FOR CONSTRUCTION ACCESS AT BRIDGE NO. 208 | 22 |
| T13.9904 | SIGNAL TIMING / COORDINATION IMPROVEMENTS | 22 |
| T15.0100 | DIRECTIONAL REGULATORY AND WARNING SIGNS | 22 |
| T15.0200 | REMOVE AND RELOCATE DIRECTIONAL REGULATORY AND WARNING SIGN | 22 |
| T20.0706 | 6 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS | 22 |
| T20.0712 | 12 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS | 23 |
| T20.0904 | 4 INCH YELLOW WATERBORNE PAINT PAVEMENT MARKINGS | 23 |
| T20.2406 | 6 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS | 23 |
| T20.2804 | 4 INCH YELLOW FINAL EPOXY RESIN PAVEMENT MARKINGS | 24 |

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
Estimate Name - Bridge Group 69E - Hunts Mills
R.I. Contract No. - 2021-CB-063
FAP Nos: BRO-0208(004)

| ItemCode | Description | Page |
|-----------------|--|-------------|
| T20.4506 | REMOVE PAVEMENT MARKING LINE - LESS THAN OR EQUAL TO 6 INCHES WIDE | 24 |
| T20.4508 | REMOVE PAVEMENT MARKING LINE - GREATER THAN 6 INCHES WIDE | 24 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|--|-----------|-----------------|----------|----------|
| 001 | 201.0321 | CLEARING AND GRUBBING | SY | | | |
| | | PLEASANT ST | | | | |
| | | NE WINGWALL | | 84.00 | 0011 | 01 |
| | | NW WINGWALL | | 62.00 | 0011 | 01 |
| | | SE WINGWALL | | 209.00 | 0011 | 01 |
| | | SW WINGWALL | | 34.00 | 0011 | 01 |
| Item 201.0321 Total: | | | | 389.00 | | |
| 002 | 201.0401 | REMOVE AND DISPOSE GRANITE CURB | LF | | | |
| | | PLEASANT ST | | | | |
| | | 15+68 TO 15+80 Lt | | 12.00 | 0011 | 01 |
| | | 16+02 LT 37' TO 16+11 LT 56' | | 20.00 | 0011 | 01 |
| Item 201.0401 Total: | | | | 32.00 | | |
| 003 | 201.0409 | REMOVE AND DISPOSE FLEXIBLE PAVEMENT | SY | | | |
| | | NE PARKING LOT | | | | |
| | | NE PARKING LOT | | 1,600.00 | 0011 | 01 |
| | | PLEASANT ST (PAVE1) | | | | |
| | | 12+00 TO BRIDGE (PAVE1) | | 321.00 | 0011 | 01 |
| | | 15+00 TO BRIDGE (PAVE1) | | 228.00 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (PAVE1) | | 75.00 | 0011 | 01 |
| | | PLEASANT ST CURB INSTALLATION | | | | |
| | | 14+14 TO 15+80 LT | | 20.00 | 0011 | 01 |
| | | LEDGE ROAD NORTH SIDE | | 3.00 | 0011 | 01 |
| Item 201.0409 Total: | | | | 2,247.00 | | |
| 004 | 201.0415 | REMOVE AND DISPOSE GUARDRAIL AND POST ALL TYPES | LF | | | |
| | | PLEASANT St | | | | |
| | | 12+35 LT TO NW END POST | | 55.00 | 0011 | 01 |
| | | 12+35 RT TO SW END POST | | 65.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|-------------|---------------|----------|----------|
| 004 | 201.0415 | Cont. | | | | |
| | | NE END POST TO 14+20 LT 70' | | 55.00 | 0011 | 01 |
| | | SE END POST TO 16+10 Rt | | 180.00 | 0011 | 01 |
| Item 201.0415 Total: | | | | 355.00 | | |
| 005 | 201.0421 | REMOVE AND DISPOSE BITUMINOUS CURB | LF | | | |
| | | LEDGE ROAD | | | | |
| | | NORTH SIDE ALONG PARKING AREA | | 110.00 | 0011 | 01 |
| Item 201.0421 Total: | | | | 110.00 | | |
| 006 | 201.0428 | REMOVE AND DISPOSE FRAME AND GRATE | EACH | | | |
| | | OR FRAME AND COVER | | | | |
| | | PLEASANT ST | | | | |
| | | 15+52 LT 85' | | 1.00 | 0011 | 01 |
| Item 201.0428 Total: | | | | 1.00 | | |
| S007 | 201.0610 | REMOVE AND DISPOSE DIRECTIONAL, | EACH | | | |
| | | WARNING, REGULATORY, SERVICE, AND | | | | |
| | | STREET SIGNS | | | | |
| | | PLEASANT ST | | | | |
| | | 15+30 RT PEDESTRIANS AHEAD | | 1.00 | 0011 | 01 |
| | | 15+47 RT STATE HIGHWAY BEGINS | | 1.00 | 0011 | 01 |
| Item 201.0610 Total: | | | | 2.00 | | |
| 008 | 201.9901 | REMOVE AND STOCKPILE TEMPORARY | LF | | | |
| | | CONCRETE BARRIER | | | | |
| | | PLEASANT ST | | | | |
| | | LEFT AND RIGHT AT BRIDGE | | 290.00 | 0011 | 01 |
| Item 201.9901 Total: | | | | 290.00 | | |
| 009 | 201.9902 | REMOVE AND STOCKPILE SHOCK | GRP | | | |
| | | ABSORBING BARRIER MODULES | | | | |
| | | PLEASANT ST | | | | |
| | | LEFT AND RIGHT AT BRIDGE | | 4.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|----------|-----------|---|------|--------|----------|----------|
| 009 | 201.9902 | Cont. | | 4.00 | | |
| | | Item 201.9902 Total: | | 4.00 | | |
| 010 | 201.9903 | REMOVE AND STOCKPILE POLYTHYLENE DRUM BARRICADES | EACH | | | |
| | | PLEASANT ST | | | | |
| | | LEFT AND RIGHT AT BRIDGE | | 12.00 | 0011 | 01 |
| | | Item 201.9903 Total: | | 12.00 | | |
| 011 | 201.9904 | REMOVE AND STOCKPILE TYPE 3 BARRICADES | EACH | | | |
| | | PLEASANT ST | | | | |
| | | LEFT AND RIGHT AT BRIDGE | | 4.00 | 0011 | 01 |
| | | Item 201.9904 Total: | | 4.00 | | |
| 012 | 201.9905 | REMOVE AND STOCKPILE SIGNS | EACH | | | |
| | | PLEASANT ST | | | | |
| | | OBJECT MARKER SIGNS | | 4.00 | 0011 | 01 |
| | | PEDESTRIAN IN SHOULDER SIGNS | | 2.00 | 0011 | 01 |
| | | SIDEWALK CLOSED SIGNS | | 4.00 | 0011 | 01 |
| | | Item 201.9905 Total: | | 10.00 | | |
| 013 | 202.0100 | EARTH EXCAVATION | CY | | | |
| | | PLEASANT ST (PAVE1) | | | | |
| | | 12+00 TO BRIDGE (PAVE1) | | 107.00 | 0011 | 01 |
| | | 15+00 TO BRIDGE (PAVE1) | | 75.99 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (PAVE1) | | 25.00 | 0011 | 01 |
| | | PLEASANT ST (PAVE2) | | | | |
| | | 11+40 TO 12+30 LT GRAVEL | | 10.00 | 0011 | 01 |
| | | PARKING APRON (PAVE2) | | | | |
| | | 14+88 TO 15+18 DRIVEWAY (PAVE2) | | 11.33 | 0011 | 01 |
| | | PLEASANT ST (PAVER) | | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|----|-----------------|----------|----------|
| 013 | 202.0100 | Cont. 15+31 TO 16+00 LT (PAVER) | | 1,988.50 | 0011 | 01 |
| | | QUANTITY | | | | |
| | | ROUNDING | | 0.18 | 0011 | 01 |
| Item 202.0100 Total: | | | | 2,218.00 | | |
| 014 | 202.0800 | GRAVEL BORROW | CY | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 400.00 | 0011 | 01 |
| Item 202.0800 Total: | | | | 400.00 | | |
| 015 | 203.0100 | STRUCTURAL EXCAVATION EARTH | CY | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 2,050.00 | 0011 | 01 |
| Item 203.0100 Total: | | | | 2,050.00 | | |
| 016 | 203.0650 | CRUSHED STONE FILL UNDER STRUCTURES | CY | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 120.00 | 0011 | 01 |
| Item 203.0650 Total: | | | | 120.00 | | |
| 017 | 203.0700 | PERVIOUS FILL | CY | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 375.00 | 0011 | 01 |
| Item 203.0700 Total: | | | | 375.00 | | |
| 018 | 204.0100 | TRIMMING AND FINE GRADING | SY | | | |
| | | PLEASANT ST (LOAM-) | | | | |
| | | 10+35 RT TO BRIDGE (LOAM-) | | 354.00 | 0011 | 01 |
| | | 12+20 LT TO BRIDGE (LOAM-) | | 256.00 | 0011 | 01 |
| | | 16+00 RT TO BRIDGE (LOAM-) | | 361.00 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (LOAM-) | | 100.00 | 0011 | 01 |
| | | NORTH SIDE FROM BRIDGE TO | | 877.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|------|-----------------|----------|----------|
| 018 | 204.0100 | Cont. | | | | |
| | | LEDGE ROAD (LOAM-) | | | | |
| | | PLEASANT ST (PAVE1) | | | | |
| | | 12+00 TO BRIDGE (PAVE1) | | 321.00 | 0011 | 01 |
| | | 15+00 TO BRIDGE (PAVE1) | | 228.00 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (PAVE1) | | 75.00 | 0011 | 01 |
| | | PLEASANT ST (PAVE2) | | | | |
| | | 11+40 TO 12+30 LT GRAVEL PARKING APRON (PAVE2) | | 30.00 | 0011 | 01 |
| | | 14+88 TO 15+18 DRIVEWAY (PAVE2) | | 34.00 | 0011 | 01 |
| | | PLEASANT ST (PAVER) | | | | |
| | | 15+31 TO 16+00 LT (PAVER) | | 441.88 | 0011 | 01 |
| | | QUANTITY ROUNDING | | 0.12 | 0011 | 01 |
| Item 204.0100 Total: | | | | 3,078.00 | | |
| 019 | 206.0312 | COMPOST FILTER SOCK 12 INCH DIAMETER | LF | | | |
| | | PLEASANT ST | | | | |
| | | 10+35 RT - SOUTH TO THE RIVER | | 280.00 | 0011 | 01 |
| | | 12+10 LT - SOUTH TO THE RIVER | | 165.00 | 0011 | 01 |
| | | 16+00 RT - NORTH TO THE RIVER | | 230.00 | 0011 | 01 |
| | | 16+15 LT 125' - NORTH TO THE RIVER | | 265.00 | 0011 | 01 |
| Item 206.0312 Total: | | | | 940.00 | | |
| 020 | 209.0200 | SACK INSERT CATCH BASIN INLET PROTECTION | EACH | | | |
| | | PLEASANT ST | | | | |
| | | 11+65 LT 16' | | 1.00 | 0011 | 01 |
| | | 15+75 LT 21' | | 1.00 | 0011 | 01 |
| | | 16+10 RT 15' | | 1.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|-------------|---------------|----------|----------|
| 020 | 209.0200 | Cont. | | | | |
| | | 16+12 LT 90' | | 1.00 | 0011 | 01 |
| | | 16+14 LT 145' | | 1.00 | 0011 | 01 |
| | | 16+40 LT 178' | | 1.00 | 0011 | 01 |
| | | 16+40 LT 90' | | 1.00 | 0011 | 01 |
| Item 209.0200 Total: | | | | 7.00 | | |
| 021 | 209.9901 | SEDIMENTATION CONTROL CURB INLET | EACH | | | |
| | | STRUCTURES | | | | |
| | | PLEASANT ST | | | | |
| | | 11+65 LT 16' | | 1.00 | 0011 | 01 |
| | | 15+75 LT 21' | | 1.00 | 0011 | 01 |
| | | 16+40 LT 178' | | 1.00 | 0011 | 01 |
| Item 209.9901 Total: | | | | 3.00 | | |
| 022 | 212.2100 | MAINTENANCE AND CLEANING OF | LS | | | |
| | | EROSION AND POLLUTION CONTROLS | | | | |
| | | PLEASANT ST | | | | |
| | | PER SPECIFICATIONS | | 1.00 | 0011 | 01 |
| Item 212.2100 Total: | | | | 1.00 | | |
| 023 | 213.0100 | PLACEMENT OF MILLINGS BENEATH | LF | | | |
| | | GUARDRAIL | | | | |
| | | PLEASANT ST | | | | |
| | | 12+35 LT TO NW END POST | | 55.00 | 0011 | 01 |
| | | 12+37 RT TO SW END POST | | 65.00 | 0011 | 01 |
| | | NE END POST TO 14+80 LT | | 65.00 | 0011 | 01 |
| | | SE END POST TO 16+10 RT | | 180.00 | 0011 | 01 |
| Item 213.0100 Total: | | | | 365.00 | | |
| 024 | 301.9901 | PEASTONE | CY | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 100.00 | 0011 | 01 |
| Item 301.9901 Total: | | | | 100.00 | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|------------|-----------------|----------|----------|
| 025 | 301.9902 | GRS REINFORCED BACKFILL | CY | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 650.00 | 0011 | 01 |
| Item 301.9902 Total: | | | | 650.00 | | |
| 026 | 302.0100 | GRAVEL BORROW SUBBASE COURSE | CY | | | |
| | | PLEASANT ST (PAVE1) | | | | |
| | | 12+00 TO BRIDGE (PAVE1) | | 107.00 | 0011 | 01 |
| | | 15+00 TO BRIDGE (PAVE1) | | 75.99 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (PAVE1) | | 25.00 | 0011 | 01 |
| | | PLEASANT ST (PAVE2) | | | | |
| | | 11+40 TO 12+30 LT GRAVEL | | 6.67 | 0011 | 01 |
| | | PARKING APRON (PAVE2) | | | | |
| | | 14+88 TO 15+18 DRIVEWAY (PAVE2) | | 7.55 | 0011 | 01 |
| | | PLEASANT ST (PAVER) | | | | |
| | | 15+31 TO 16+00 LT (PAVER) | | 1,325.65 | 0011 | 01 |
| | | QUANTITY | | | | |
| | | ROUNDING | | 0.14 | 0011 | 01 |
| Item 302.0100 Total: | | | | 1,548.00 | | |
| 027 | 401.1000 | CLASS 19.0 HMA | TON | | | |
| | | PLEASANT ST | | | | |
| | | ROUNDING | | 0.30 | 0011 | 01 |
| | | PLEASANT ST (PAVE1) | | | | |
| | | 12+00 TO BRIDGE (PAVE1) | | 179.87 | 0011 | 01 |
| | | 15+00 TO BRIDGE (PAVE1) | | 127.76 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (PAVE1) | | 42.03 | 0011 | 01 |
| | | PLEASANT ST (PAVE2) | | | | |
| | | 11+40 TO 12+30 LT GRAVEL | | 5.60 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|------------|---------------|----------|----------|
| 027 | 401.1000 | Cont. | | | | |
| | | PARKING APRON (PAVE2) | | | | |
| | | 14+88 TO 15+18 DRIVEWAY | | 6.35 | 0011 | 01 |
| | | (PAVE2) | | | | |
| | | QUANTITY | | | | |
| | | ROUNDING | | 0.09 | 0011 | 01 |
| Item 401.1000 Total: | | | | 362.00 | | |
| 028 | 401.3101 | MODIFIED CLASS 9.5 HMA FOR BRIDGE DECKS | TON | | | |
| | | PLEASANT ST (MICRO) | | | | |
| | | 10+35 TO 12+50 (MICRO) | | 82.50 | 0011 | 01 |
| | | 14+50 TO 15+80 (MICRO) | | 48.44 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (MICRO) | | 13.32 | 0011 | 01 |
| | | PLEASANT ST (PAVE1) | | | | |
| | | 12+00 TO BRIDGE (PAVE1) | | 30.55 | 0011 | 01 |
| | | 15+00 TO BRIDGE (PAVE1) | | 21.70 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (PAVE1) | | 7.14 | 0011 | 01 |
| | | PLEASANT ST (PAVE2) | | | | |
| | | 11+40 TO 12+30 LT GRAVEL | | 2.85 | 0011 | 01 |
| | | PARKING APRON (PAVE2) | | | | |
| | | 14+88 TO 15+18 DRIVEWAY | | 3.24 | 0011 | 01 |
| | | (PAVE2) | | | | |
| | | QUANTITY | | | | |
| | | ROUNDING | | 0.26 | 0011 | 01 |
| Item 401.3101 Total: | | | | 210.00 | | |
| 029 | 403.0300 | ASPHALT EMULSION TACK COAT | SY | | | |
| | | PLEASANT ST (MICRO) | | | | |
| | | 10+35 TO 12+50 (MICRO) | | 867.00 | 0011 | 01 |
| | | 14+50 TO 15+80 (MICRO) | | 509.00 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD | | 140.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|-----------------------------------|-----|-----------------|----------|----------|
| 029 | 403.0300 | Cont. | | | | |
| | | CONDITIONS (MICRO) | | | | |
| | | PLEASANT ST (PAVE1) | | | | |
| | | 12+00 TO BRIDGE (PAVE1) | | 642.00 | 0011 | 01 |
| | | 15+00 TO BRIDGE (PAVE1) | | 456.00 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD | | 150.00 | 0011 | 01 |
| | | CONDITIONS (PAVE1) | | | | |
| | | PLEASANT ST (PAVE2) | | | | |
| | | 11+40 TO 12+30 LT GRAVEL | | 60.00 | 0011 | 01 |
| | | PARKING APRON (PAVE2) | | | | |
| | | 14+88 TO 15+18 DRIVEWAY | | 68.00 | 0011 | 01 |
| | | (PAVE2) | | | | |
| Item 403.0300 Total: | | | | 2,892.00 | | |
| 030 | 410.1000 | TEMPORARY PATCHING | TON | | | |
| | | MATERIAL/TRENCHES | | | | |
| | | PLEASANT ST | | | | |
| | | PATCHING | | 15.00 | 0011 | 01 |
| Item 410.1000 Total: | | | | 15.00 | | |
| 031 | 601.0200 | CLASS XX PORTLAND CEMENT CONCRETE | CY | | | |
| | | PLEASANT STREET CURB LOCK | | | | |
| | | 14+14 TO 15+80 LT | | 7.00 | 0011 | 01 |
| | | LEDGE ROAD NORTH SIDE | | 2.00 | 0011 | 01 |
| Item 601.0200 Total: | | | | 9.00 | | |
| 032 | 603.1000 | CONTROLLED LOW STRENGTH MATERIAL | CY | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 70.00 | 0011 | 01 |
| Item 603.1000 Total: | | | | 70.00 | | |
| 033 | 701.0412 | REINFORCED CONCRETE PIPE M 170 | LF | | | |
| | | CLASS III 12 INCH | | | | |
| | | PLEASANT ST | | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|-------------|--------------|----------|----------|
| 033 | 701.0412 | Cont. 15+75 LT 21' TO 15+50 LT 85' | | 64.00 | 0011 | 01 |
| Item 701.0412 Total: | | | | 64.00 | | |
| 034 | 702.0516 | FRAME AND GRATE, HIGH CAPACITY, STANDARD 6.3.4 | EACH | | | |
| | | PLEASANT ST 15+75 LT 15' | | 1.00 | 0011 | 01 |
| Item 702.0516 Total: | | | | 1.00 | | |
| 035 | 702.0522 | FRAME AND COVER STANDARD 6.2.1 | EACH | | | |
| | | PLEASANT ST 15+50 LT 85' | | 1.00 | 0011 | 01 |
| Item 702.0522 Total: | | | | 1.00 | | |
| 036 | 702.0543 | GRANITE APRON STONE 38'' STANDARD | EACH | | | |
| | | 7.3.8 PLEASANT ST 15+75 LT 21' | | 1.00 | 0011 | 01 |
| Item 702.0543 Total: | | | | 1.00 | | |
| 037 | 702.0840 | ALTERNATE TOP COVER ROUND PRECAST MANHOLES AND CATCH BASINS STANDARD | EACH | | | |
| | | 4.7.2 PLEASANT ST 15+75 LT 21' | | 1.00 | 0011 | 01 |
| Item 702.0840 Total: | | | | 1.00 | | |
| 038 | 702.9901 | MODIFIED PRECAST 4'-0" ROUND CATCH BASIN WITH 4'-0" DEEP SUMP STD | EACH | | | |
| | | 4.4.0M PLEASANT ST 15+75 LT 21' | | 1.00 | 0011 | 01 |
| Item 702.9901 Total: | | | | 1.00 | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|------|---------------|----------|----------|
| 039 | 702.9902 | PERMEABLE PAVER SAND FILTER SYSTEM | LS | | | |
| | | PLEASANT ST | | | | |
| | | 14+36 TO 15+31 LT | | 1.00 | 0011 | 01 |
| Item 702.9902 Total: | | | | 1.00 | | |
| 040 | 707.1200 | ADJUST CATCH BASIN TO MANHOLE | EACH | | | |
| | | PLEASANT ST | | | | |
| | | 15+50 LT 85' | | 1.00 | 0011 | 01 |
| Item 707.1200 Total: | | | | 1.00 | | |
| 041 | 708.9040 | CLEANING AND FLUSHING PIPE ALL SIZES | LF | | | |
| | | PLEASANT ST | | | | |
| | | 11+65 LT - RT | | 45.00 | 0011 | 01 |
| | | 15+52 LT 83' TO 15+65 LT | | 50.00 | 0011 | 01 |
| | | 120' 36" RCP | | | | |
| | | 15+52 LT 83' TO RIVER 36" RCP | | 177.00 | 0011 | 01 |
| | | 15+65 LT 120' TO 16+12 LT | | 45.00 | 0011 | 01 |
| | | 90' 12" RCP | | | | |
| | | 15+65 LT 120' TO 16+14 LT | | 45.00 | 0011 | 01 |
| | | 145' 12" RCP | | | | |
| | | 16+08 RT | | 20.00 | 0011 | 01 |
| | | 16+12 LT 90' TO 16+40 LT 90' | | 35.00 | 0011 | 01 |
| | | 12" RCP | | | | |
| | | 16+14 LT 145' TO 16+26 LT | | 45.00 | 0011 | 01 |
| | | 180' 12" RCP | | | | |
| Item 708.9040 Total: | | | | 462.00 | | |
| 042 | 708.9041 | CLEANING CATCH BASINS ALL TYPES AND SIZES | EACH | | | |
| | | PLEASANT ST | | | | |
| | | 11+65 LT 16' | | 1.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|----------------|---|-------------|--------------|----------|----------|
| 042 | 708.9041 Cont. | 15+52 LT 85' | | 1.00 | 0011 | 01 |
| | | 16+10 RT 15' | | 1.00 | 0011 | 01 |
| | | 16+12 LT 90' | | 1.00 | 0011 | 01 |
| | | 16+14 LT 145' | | 1.00 | 0011 | 01 |
| | | 16+40 LT 178' | | 1.00 | 0011 | 01 |
| | | 16+40 LT 90' | | 1.00 | 0011 | 01 |
| Item 708.9041 Total: | | | | 7.00 | | |
| 043 | 708.9042 | CLEANING MANHOLES ALL TYPES AND SIZES | EACH | | | |
| | | PLEASANT ST | | | | |
| | | 15+90 LT 120' | | 1.00 | 0011 | 01 |
| Item 708.9042 Total: | | | | 1.00 | | |
| 044 | 800.9901 | HUNTS MILLS BRIDGE NO. 208 | LS | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 1.00 | 0011 | 01 |
| Item 800.9901 Total: | | | | 1.00 | | |
| 045 | 803.9901 | REMOVE AND DISPOSE EXISTING HUNTS MILLS BRIDGE NO. 208 | LS | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 1.00 | 0011 | 01 |
| Item 803.9901 Total: | | | | 1.00 | | |
| 046 | 804.9901 | DRILLED MICROPILES | EACH | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 96.00 | 0011 | 01 |
| Item 804.9901 Total: | | | | 96.00 | | |
| 047 | 808.0321 | CONCRETE SUBSTRUCTURE CLASS HP 3/4'' WALL CAP | CY | | | |
| | | BRIDGE NO. 208 | | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|----------------------|-----------|--|------|----------|----------|----------|
| 047 | 808.0321 | Cont. BRIDGE NO. 208 | | 22.00 | 0011 | 01 |
| Item 808.0321 Total: | | | | 22.00 | | |
| 048 | 810.0702 | WELDED WIRE FABRIC (GALVANIZED) BRIDGE NO. 208 | SF | | | |
| | | BRIDGE NO. 208 | | 1,400.00 | 0011 | 01 |
| Item 810.0702 Total: | | | | 1,400.00 | | |
| 049 | 817.9901 | REMOVE, SALVAGE AND DELIVER IDENTIFICATION TILES BRIDGE NO. 208 | EACH | | | |
| | | BRIDGE NO. 208 | | 2.00 | 0011 | 01 |
| Item 817.9901 Total: | | | | 2.00 | | |
| 050 | 819.0800 | DRILL AND GROUT REINFORCING DOWELS BRIDGE NO. 208 | EACH | | | |
| | | BRIDGE NO. 208 | | 100.00 | 0011 | 01 |
| Item 819.0800 Total: | | | | 100.00 | | |
| S051 | 901.0101 | GUARDRAIL STEEL BEAM SINGLE FACE EARTH AND ASPHALT PLEASANT ST | LF | | | |
| | | 14+55 TO 15+80 RT | | 125.00 | 0011 | 01 |
| Item 901.0101 Total: | | | | 125.00 | | |
| S052 | 901.9901 | GUARDRAIL CONNECTION TO END POST APPROACH SECTION WITH NESTED RAIL PLEASANT ST | EACH | | | |
| | | NE END POST | | 1.00 | 0011 | 01 |
| | | SW END POST | | 1.00 | 0011 | 01 |
| Item 901.9901 Total: | | | | 2.00 | | |
| S053 | 901.9902 | GUARDRAIL CONNECTION TO END POST | EACH | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|------|---------------|----------|----------|
| S053 | 901.9902 | Cont. TRAILING END SECTION WITHOUT NESTED RAIL PLEASANT ST | | | | |
| | | NW END POST | | 1.00 | 0011 | 01 |
| | | SE END POST | | 1.00 | 0011 | 01 |
| Item 901.9902 Total: | | | | 2.00 | | |
| S054 | 901.9903 | GUARDRAIL END TREATMENT MASH COMPLIANT TEST LEVEL 3 PLEASANT ST | EACH | | | |
| | | 12+35 LT | | 1.00 | 0011 | 01 |
| | | 12+37 RT | | 1.00 | 0011 | 01 |
| | | 14+80 LT | | 1.00 | 0011 | 01 |
| | | 16+10 RT | | 1.00 | 0011 | 01 |
| Item 901.9903 Total: | | | | 4.00 | | |
| S055 | 903.0410 | TEMPORARY CHAIN LINK FENCE PLEASANT ST | LF | | | |
| | | BRIDGE CLOSURE | | 480.00 | 0011 | 01 |
| | | LANE SHIFT WITH TEMPORARY BARRIER | | 510.00 | 0011 | 01 |
| Item 903.0410 Total: | | | | 990.00 | | |
| 056 | 906.0110 | GRANITE CURB, QUARRY SPLIT STRAIGHT, STANDARD 7.3.0 PLEASANT ST | LF | | | |
| | | 14+15 TO 14+82 Lt | | 67.00 | 0011 | 01 |
| | | 15+24 TO 15+74 Lt | | 50.00 | 0011 | 01 |
| Item 906.0110 Total: | | | | 117.00 | | |
| 057 | 906.0111 | GRANITE CURB, QUARRY SPLIT CIRCULAR, STANDARD 7.3.0 PLEASANT ST | LF | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|------|-----------------|----------|----------|
| 057 | 906.0111 | Cont. 16+02 LT 37' TO 16+11 LT 56' (R=50'+/-) | | 20.00 | 0011 | 01 |
| Item 906.0111 Total: | | | | 20.00 | | |
| 058 | 906.0118 | 6' GRANITE TRANSITION CURB, QUARRY SPLIT SPECIAL TRANSITION STANDARD 7.3.2 PLEASANT ST 14+82 TO 14+88 Lt 15+18 TO 15+24 Lt NW BRIDGE SIDEWALK SE BRIDGE SIDEWALK SW BRIDGE SIDEWALK | EACH | | | |
| | | | | 1.00 | 0011 | 01 |
| | | | | 1.00 | 0011 | 01 |
| | | | | 1.00 | 0011 | 01 |
| | | | | 1.00 | 0011 | 01 |
| | | | | 1.00 | 0011 | 01 |
| Item 906.0118 Total: | | | | 5.00 | | |
| 059 | 906.0210 | CEMENT CONCRETE CURB PRECAST STRAIGHT STANDARD 7.1.0 PLEASANT ST CONCRETE BLOCK PAVERS | LF | | | |
| | | | | 400.00 | 0011 | 01 |
| Item 906.0210 Total: | | | | 400.00 | | |
| 060 | 906.9901 | CONCRETE BLOCK PAVERS PLEASANT ST (PAVER) 15+31 TO 16+00 LT (PAVER) | SF | | | |
| | | | | 3,977.00 | 0011 | 01 |
| Item 906.9901 Total: | | | | 3,977.00 | | |
| 061 | 907.0100 | WATER FOR DUST CONTROL PLEASANT ST PER SPECIFICATIONS | MGAL | | | |
| | | | | 21.00 | 0011 | 01 |
| Item 907.0100 Total: | | | | 21.00 | | |
| 062 | 914.5010 | FLAGPERSONS PLEASANT ST | MHRS | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|----------------|--|-------------|---------------|----------|----------|
| 062 | 914.5010 Cont. | TRAFFIC CONTROL | | 640.00 | 0011 | 01 |
| Item 914.5010 Total: | | | | 640.00 | | |
| 063 | 914.5020 | FLAGPERSONS - OVERTIME | MHRS | | | |
| | | PLEASANT ST | | | | |
| | | TRAFFIC CONTROL | | 64.00 | 0011 | 01 |
| Item 914.5020 Total: | | | | 64.00 | | |
| 064 | 916.0600 | SHOCK ABSORBING BARRIER MODULES | GRP | | | |
| | | PLEASANT ST | | | | |
| | | TEMPORARY TRAFFIC CONTROL | | 4.00 | 0011 | 01 |
| Item 916.0600 Total: | | | | 4.00 | | |
| 065 | 919.0101 | TEST PITS | EACH | | | |
| | | PLEASANT ST | | | | |
| | | PER SPECIFICATIONS | | 2.00 | 0011 | 01 |
| Item 919.0101 Total: | | | | 2.00 | | |
| 066 | 920.0040 | DUMPED STONE RIPRAP R-3, R-4, R-5 | SY | | | |
| | | STANDARD 8.3.0 | | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 120.00 | 0011 | 01 |
| Item 920.0040 Total: | | | | 120.00 | | |
| 067 | 920.0135 | BEDDING FOR RIPRAP FS-2 STANDARD | SY | | | |
| | | 8.3.0 | | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 120.00 | 0011 | 01 |
| Item 920.0135 Total: | | | | 120.00 | | |
| 068 | 920.0200 | FILTER FABRIC FOR RIP-RAP | SY | | | |
| | | BRIDGE NO. 208 | | | | |
| | | BRIDGE NO. 208 | | 120.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|----------------------|-----------|--|----|--------|----------|----------|
| 068 | 920.0200 | Cont. | | 120.00 | | |
| Item 920.0200 Total: | | | | | | |
| 069 | 922.0100 | TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1 | SF | | | |
| | | PLEASANT ST | | | | |
| | | TEMPORARY TRAFFIC CONTROL | | 100.00 | 0011 | 01 |
| | | PLEASANT ST DETOUR | | | | |
| | | M1-5 RI ROUTE 114A 30X24 (13) | | 65.00 | 0011 | 01 |
| | | M3-1 NORTH 24X12 (9) | | 18.00 | 0011 | 01 |
| | | M3-3 SOUTH 24X12 (4) | | 8.00 | 0011 | 01 |
| | | M4-10R DETOUR ARROW RIGHT 48X18 (1) | | 6.00 | 0011 | 01 |
| | | M4-8 DETOUR 24X12 (13) | | 26.00 | 0011 | 01 |
| | | M4-8A END DETOUR 24X12 (3) | | 6.00 | 0011 | 01 |
| | | M6-1L LEFT ARROW 21X15 (6) | | 18.00 | 0011 | 01 |
| | | M6-1R RIGHT ARROW 21X15 (4) | | 12.00 | 0011 | 01 |
| | | M6-3 STRAIGHT ARROW 21X15 (3) | | 9.00 | 0011 | 01 |
| | | R11-2 ROAD CLOSED 48X30 (2) | | 20.00 | 0011 | 01 |
| | | R11-3A ROAD CLOSED AHEAD LOCAL TRAFFIC ONLY 60X30 (2) | | 25.00 | 0011 | 01 |
| | | SPECIAL-1 PLEASANT ST CLOSED AHEAD 48X24 (2) | | 16.00 | 0011 | 01 |
| | | SPECIAL-2 PLEASANT ST CLOSED 48X24 (1) | | 8.00 | 0011 | 01 |
| | | W20-1 ROAD WORK AHEAD 36X36 (1) | | 9.00 | 0011 | 01 |
| | | W20-2 DETOUR AHEAD 36X36 (5) | | 45.00 | 0011 | 01 |
| | | W20-3 ROAD CLOSED AHEAD 36X36 (1) | | 9.00 | 0011 | 01 |
| | | PLEASANT ST LANE SHIFT | | | | |
| | | R9-11L SIDEWALK CLOSED 24X12 (1) | | 2.00 | 0011 | 01 |
| | | R9-11R SIDEWALK CLOSED 24X12 | | 2.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|--|--------------|-----------------|----------|----------|
| 069 | 922.0100 | Cont. | (1) | | | |
| | | W11-2 PEDESTRIAN 30X30 | (4) | 28.00 | 0011 | 01 |
| | | W1-4L LANE SHIFT 36X36 | (1) | 9.00 | 0011 | 01 |
| | | W1-4R LANE SHIFT 36X36 | (1) | 9.00 | 0011 | 01 |
| | | W16-7P ARROW 24X12 | (2) | 4.00 | 0011 | 01 |
| | | W16-9P AHEAD 24X12 | (2) | 4.00 | 0011 | 01 |
| | | PLEASANT ST ONE LANE ALTERNATING TRAFFIC | | | | |
| | | G20-2 END ROAD WORK 36X18 | (2) | 9.00 | 0011 | 01 |
| | | STD 27.1.1 WORK ZONE FINES 36X54 | (2) | 42.00 | 0011 | 01 |
| | | W20-1 ROAD WORK AHEAD 36X36 | (4) | 45.00 | 0011 | 01 |
| | | W20-4 ONE LANE ROAD AHEAD 36X36 (@) | | 27.00 | 0011 | 01 |
| | | W20-7A FLAGPERSON 36X36 | (2) | 27.00 | 0011 | 01 |
| Item 922.0100 Total: | | | | 608.00 | | |
| 070 | 923.0105 | DRUM BARRICADE STANDARD 26.2.0 | B DAY | | | |
| | | PLEASANT ST TEMPORARY TRAFFIC CONTROL | | 8,400.00 | 0011 | 01 |
| Item 923.0105 Total: | | | | 8,400.00 | | |
| 071 | 923.0120 | PLASTIC PIPE BARRICADE STANDARD 26.3.0 | EACH | | | |
| | | PLEASANT ST TEMPORARY TRAFFIC CONTROL | | 4.00 | 0011 | 01 |
| Item 923.0120 Total: | | | | 4.00 | | |
| 072 | 923.0200 | FLUORESCENT TRAFFIC CONES STANDARD 26.1.0 | EACH | | | |
| | | PLEASANT ST TEMPORARY TRAFFIC CONTROL | | 100.00 | 0011 | 01 |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|----------|-----------|----------------------------------|------|----------|----------|----------|
| 072 | 923.0200 | Cont. | | | | |
| | | Item 923.0200 Total: | | 100.00 | | |
| 073 | 925.0112 | PORTABLE CHANGEABLE MESSAGE SIGN | PDAY | | | |
| | | PLEASANT ST | | | | |
| | | TEMPORARY TRAFFIC CONTROL | | 1,260.00 | 0011 | 01 |
| | | Item 925.0112 Total: | | 1,260.00 | | |
| 074 | 926.0140 | REFLECTIVE DELINEATORS FOR | EACH | | | |
| | | TEMPORARY CONCRETE BARRIERS | | | | |
| | | PLEASANT ST | | | | |
| | | TEMPORARY TRAFFIC CONTROL | | 36.00 | 0011 | 01 |
| | | Item 926.0140 Total: | | 36.00 | | |
| 075 | 926.9901 | UNANCORED BARRIER FOR TEMPORARY | LF | | | |
| | | TRAFFIC CONTROL TEST LEVEL 3 | | | | |
| | | PLEASANT ST | | | | |
| | | LANE SHIFT WITH TEMPORARY | | 640.00 | 0011 | 01 |
| | | BARRIER | | | | |
| | | STREET CLOSURE | | 80.00 | 0011 | 01 |
| | | Item 926.9901 Total: | | 720.00 | | |
| 076 | 929.0110 | FIELD OFFICE | PMO | | | |
| | | PLEASANT ST | | | | |
| | | PER SPECIFICATIONS | | 20.00 | 0011 | 01 |
| | | Item 929.0110 Total: | | 20.00 | | |
| 077 | 931.0110 | CLEANING AND SWEEPING PAVEMENT | HSY | | | |
| | | PLEASANT ST | | | | |
| | | PAVEMENT AREA | | 50.00 | 0011 | 01 |
| | | Item 931.0110 Total: | | 50.00 | | |
| 078 | 932.0100 | CUTTING AND MATCHING ASPHALT | LF | | | |
| | | PLEASANT ST | | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|--|-----------|-----------------|----------|----------|
| 078 | 932.0100 | Cont. | | | | |
| | | 10+35 LT - RT | | 43.00 | 0011 | 01 |
| | | 15+80 LT - RT | | 37.00 | 0011 | 01 |
| Item 932.0100 Total: | | | | 80.00 | | |
| 079 | 932.0200 | FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT | LF | | | |
| | | LEDGE ROAD | | | | |
| | | NORTH SIDE ALONG CURB | | 25.00 | 0011 | 01 |
| | | PLEASANT ST | | | | |
| | | 12+00 TO 12+50 LT | | 56.00 | 0011 | 01 |
| | | 12+00 TO 12+50 RT | | 56.00 | 0011 | 01 |
| | | 12+50 LT - RT | | 40.00 | 0011 | 01 |
| | | 14+14 TO 15+80 LT | | 166.00 | 0011 | 01 |
| | | 14+50 LT - RT | | 40.00 | 0011 | 01 |
| | | 14+50 TO 15+00 RT | | 53.00 | 0011 | 01 |
| Item 932.0200 Total: | | | | 436.00 | | |
| 080 | 935.0400 | REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING | SY | | | |
| | | PLEASANT ST (MICRO) | | | | |
| | | 10+35 TO 12+50 (MICRO) | | 867.00 | 0011 | 01 |
| | | 14+50 TO 15+80 (MICRO) | | 509.00 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD CONDITIONS (MICRO) | | 140.00 | 0011 | 01 |
| Item 935.0400 Total: | | | | 1,516.00 | | |
| 081 | 936.0100 | MOBILIZATION AND DEMOBILIZATION | LS | | | |
| | | PLEASANT STREET | | | | |
| | | PER SPECIFICATIONS | | 1.00 | 0011 | 01 |
| Item 936.0100 Total: | | | | 1.00 | | |
| 082 | 937.0200 | MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION | LS | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|----------------|-------------------------------------|-------------|-----------------|----------|----------|
| 082 | 937.0200 Cont. | PLEASANT ST | | | | |
| | | TEMPORARY TRAFFIC CONTROL | | 1.00 | 0011 | 01 |
| Item 937.0200 Total: | | | | 1.00 | | |
| 083 | 943.0200 | TRAINEE MAN-HOURS | MHRS | | | |
| | | PLEASANT ST | | | | |
| | | PER SPECIFICATIONS | | 1,500.00 | 0011 | 01 |
| Item 943.0200 Total: | | | | 1,500.00 | | |
| 084 | L01.0102 | LOAM BORROW 4 INCHES DEEP | SY | | | |
| | | PLEASANT ST (LOAM-) | | | | |
| | | 10+35 RT TO BRIDGE (LOAM-) | | 354.00 | 0011 | 01 |
| | | 12+20 LT TO BRIDGE (LOAM-) | | 256.00 | 0011 | 01 |
| | | 16+00 RT TO BRIDGE (LOAM-) | | 361.00 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD | | 100.00 | 0011 | 01 |
| | | CONDITIONS (LOAM-) | | | | |
| | | NORTH SIDE FROM BRIDGE TO | | 877.00 | 0011 | 01 |
| | | LEDGE ROAD (LOAM-) | | | | |
| Item L01.0102 Total: | | | | 1,948.00 | | |
| S085 | L02.0102 | RESIDENTIAL SEEDING (TYPE 2) | SY | | | |
| | | PLEASANT ST (LOAM-) | | | | |
| | | 10+35 RT TO BRIDGE (LOAM-) | | 354.00 | 0011 | 01 |
| | | 12+20 LT TO BRIDGE (LOAM-) | | 256.00 | 0011 | 01 |
| | | 16+00 RT TO BRIDGE (LOAM-) | | 361.00 | 0011 | 01 |
| | | INCREASE DUE TO ACTUAL FIELD | | 100.00 | 0011 | 01 |
| | | CONDITIONS (LOAM-) | | | | |
| | | NORTH SIDE FROM BRIDGE TO | | 877.00 | 0011 | 01 |
| | | LEDGE ROAD (LOAM-) | | | | |
| Item L02.0102 Total: | | | | 1,948.00 | | |
| 086 | L08.0109 | TREE TRIMMING | MHRS | | | |
| | | PLEASANT ST | | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|---|------|---------------|----------|----------|
| 086 | L08.0109 | Cont. TEMPORARY AND PERMANENT UTILITY POLES | | 32.00 | 0011 | 01 |
| Item L08.0109 Total: | | | | 32.00 | | |
| 087 | L09.9901 | SELECTIVE CLEARING FOR CONSTRUCTION ACCESS AT BRIDGE NO. 208 PLEASANT STREET CONTINGENCY | SY | | | |
| | | | | 200.00 | 0011 | 01 |
| Item L09.9901 Total: | | | | 200.00 | | |
| 088 | T13.9904 | SIGNAL TIMING / COORDINATION IMPROVEMENTS PROJECTWIDE AS DIRECTED BY ENGINEER | LS | | | |
| | | | | 1.00 | 0011 | 01 |
| Item T13.9904 Total: | | | | 1.00 | | |
| S089 | T15.0100 | DIRECTIONAL REGULATORY AND WARNING SIGNS PLEASANT ST 1-1 (W11-2) 36X36 1-1 (W16-9P) 24X12 1-2 (MA-1-13) 24X30 | SF | | | |
| | | | | 9.00 | 0011 | 01 |
| | | | | 2.00 | 0011 | 01 |
| | | | | 5.00 | 0011 | 01 |
| Item T15.0100 Total: | | | | 16.00 | | |
| S090 | T15.0200 | REMOVE AND RELOCATE DIRECTIONAL REGULATORY AND WARNING SIGN PLEASANT ST 12+30 LT ADOPT A HIGHWAY 14+60 RT ADOPT A HIGHWAY | EACH | | | |
| | | | | 1.00 | 0011 | 01 |
| | | | | 1.00 | 0011 | 01 |
| Item T15.0200 Total: | | | | 2.00 | | |
| S091 | T20.0706 | 6 INCH WHITE WATERBORNE PAINT | LF | | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|-----------------------------|-----------|--------------------------------|----|-----------------|----------|----------|
| S091 | T20.0706 | Cont. PAVEMENT MARKINGS | | | | |
| | | PLEASANT ST | | | | |
| | | FINAL SURFACE BEFORE EPOXY | | 1,090.00 | 0011 | 01 |
| | | RESIN | | | | |
| | | LANE SHIFT WITH TEMPORARY | | 1,090.00 | 0011 | 01 |
| | | BARRIER | | | | |
| | | MILLED SURFACE OR BASE COURSE | | 1,090.00 | 0011 | 01 |
| Item T20.0706 Total: | | | | 3,270.00 | | |
| S092 | T20.0712 | 12 INCH WHITE WATERBORNE PAINT | LF | | | |
| | | PAVEMENT MARKINGS | | | | |
| | | PLEASANT ST | | | | |
| | | TEMPORARY CROSSWALK AT HUNTS | | 112.00 | 0011 | 01 |
| | | MILL ROAD | | | | |
| Item T20.0712 Total: | | | | 112.00 | | |
| S093 | T20.0904 | 4 INCH YELLOW WATERBORNE PAINT | LF | | | |
| | | PAVEMENT MARKINGS | | | | |
| | | PLEASANT ST | | | | |
| | | FINAL SURFACE BEFORE EPOXY | | 1,090.00 | 0011 | 01 |
| | | RESIN | | | | |
| | | LANE SHIFT WITH TEMPORARY | | 1,090.00 | 0011 | 01 |
| | | BARRIER | | | | |
| | | MILLED SURFACE OR BASE COURSE | | 1,090.00 | 0011 | 01 |
| Item T20.0904 Total: | | | | 3,270.00 | | |
| S094 | T20.2406 | 6 INCH WHITE FINAL EPOXY RESIN | LF | | | |
| | | PAVEMENT MARKINGS | | | | |
| | | PLEASANT ST | | | | |
| | | 10+35 TO 15+80 LT | | 545.00 | 0011 | 01 |
| | | 10+35 TO 15+80 RT | | 545.00 | 0011 | 01 |
| Item T20.2406 Total: | | | | 1,090.00 | | |

Distribution of Quantities

Project Name - Bridge Group 69E - Hunts Mills
 Estimate Name - Bridge Group 69E - Hunts Mills
 R.I. Contract No. - 2021-CB-063
 FAP Nos: BRO-0208(004)

| Item No. | Item Code | Description | UM | Qty. | Pay Code | Seq. No. |
|----------|-----------|----------------------------------|----|-----------------|----------|----------|
| S095 | T20.2804 | 4 INCH YELLOW FINAL EPOXY RESIN | LF | | | |
| | | PAVEMENT MARKINGS | | | | |
| | | PLEASANT ST | | | | |
| | | 10+35 TO 15+80 | | 1,090.00 | 0011 | 01 |
| | | Item T20.2804 Total: | | 1,090.00 | | |
| S096 | T20.4506 | REMOVE PAVEMENT MARKING LINE - | LF | | | |
| | | LESS THAN OR EQUAL TO 6 INCHES | | | | |
| | | WIDE | | | | |
| | | PLEASANT ST EXISTING PAVEMENT | | | | |
| | | MARKING LINES | | | | |
| | | 10+35 TO 15+80 CENTER LINES | | 1,090.00 | 0011 | 01 |
| | | 10+35 TO 15+80 SHOULDER LINES | | 1,090.00 | 0011 | 01 |
| | | PLEASANT ST TEMPORARY LANE SHIFT | | | | |
| | | 10+35 TO 15+80 CENTER LINES | | 1,090.00 | 0011 | 01 |
| | | 10+35 TO 15+80 SHOULDER LINES | | 1,090.00 | 0011 | 01 |
| | | Item T20.4506 Total: | | 4,360.00 | | |
| S097 | T20.4508 | REMOVE PAVEMENT MARKING LINE - | LF | | | |
| | | GREATER THAN 6 INCHES WIDE | | | | |
| | | PLEASANT ST | | | | |
| | | TEMPORARY CROSSWALK AT HUNTS | | 112.00 | 0011 | 01 |
| | | MILL ROAD | | | | |
| | | Item T20.4508 Total: | | 112.00 | | |

Assembly Summary

Project Name: Bridge Group 69E - Hunts Mills

Estimate Name: Bridge Group 69E - Hunts Mills

R.I. Contract No.: 2021-CB-063

FAP Nos.:BRO-0208(004)

| Item Code | Description | Depth | Factor | Qty |
|--|---|-------|---------|--------|
| <u>Assembly: LOAM AND SEEDING TYPE 2 (LOAM-) (Unit: SY Default Quantity: 1948.00)</u> | | | | |
| 204.0100 | TRIMMING AND FINE GRADING | | 1.00000 | |
| L01.0102 | LOAM BORROW 4 INCHES DEEP | 4" | 1.00000 | |
| L02.0102 | RESIDENTIAL SEEDING (TYPE 2) | | 1.00000 | |
| | PLEASANT ST (LOAM-) | | | |
| | 12+20 LT TO BRIDGE (LOAM-) | | | 256.00 |
| | 10+35 RT TO BRIDGE (LOAM-) | | | 354.00 |
| | 16+00 RT TO BRIDGE (LOAM-) | | | 361.00 |
| | INCREASE DUE TO ACTUAL FIELD CONDITIONS (LOAM-) | | | 100.00 |
| | NORTH SIDE FROM BRIDGE TO LEDGE ROAD (LOAM-) | | | 877.00 |
| <u>Assembly: PAVEMENT TYPE P (MICRO) (Unit: SY Default Quantity: 1516.00)</u> | | | | |
| 401.3101 | MODIFIED CLASS 9.5 HMA FOR BRIDGE DECKS | 1.5" | 0.09516 | |
| 403.0300 | ASPHALT EMULSION TACK COAT | | 1.00000 | |
| 935.0400 | REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING | 1.5" | 1.00000 | |
| | PLEASANT ST (MICRO) | | | |
| | INCREASE DUE TO ACTUAL FIELD CONDITIONS (MICRO) | | | 140.00 |
| | 10+35 TO 12+50 (MICRO) | | | 867.00 |
| | 14+50 TO 15+80 (MICRO) | | | 509.00 |
| <u>Assembly: PAVEMENT TYPE P-1 (PAVE1) (Unit: SY Default Quantity: 624.00)</u> | | | | |
| 201.0409 | REMOVE AND DISPOSE FLEXIBLE PAVEMENT | | 1.00000 | |
| 202.0100 | EARTH EXCAVATION | 12" | 0.33333 | |
| 204.0100 | TRIMMING AND FINE GRADING | | 1.00000 | |
| 302.0100 | GRAVEL BORROW SUBBASE COURSE | 12" | 0.33333 | |
| 401.1000 | CLASS 19.0 HMA | 6" | 0.56034 | |
| 401.3101 | MODIFIED CLASS 9.5 HMA FOR BRIDGE DECKS | 1.5" | 0.09516 | |
| 403.0300 | ASPHALT EMULSION TACK COAT | | 2.00000 | |
| | PLEASANT ST (PAVE1) | | | |
| | INCREASE DUE TO ACTUAL FIELD CONDITIONS (PAVE1) | | | 75.00 |
| | 12+00 TO BRIDGE (PAVE1) | | | 321.00 |
| | 15+00 TO BRIDGE (PAVE1) | | | 228.00 |

Assembly Summary

Project Name:

Estimate Name:

R.I. Contract No.:

FAP Nos.:

| Item Code | Description | Depth | Factor | Qty |
|--|--|-------|---------|---------|
| <u>Assembly: PAVEMENT TYPE P-2 (PAVE2) (Unit: SY Default Quantity: 64.00)</u> | | | | |
| 202.0100 | EARTH EXCAVATION | 12" | 0.33333 | |
| 204.0100 | TRIMMING AND FINE GRADING | | 1.00000 | |
| 302.0100 | GRAVEL BORROW SUBBASE COURSE | 8" | 0.22222 | |
| 401.1000 | CLASS 19.0 HMA | 3" | 0.18678 | |
| 401.3101 | MODIFIED CLASS 9.5 HMA FOR BRIDGE DECKS | 1.5" | 0.09516 | |
| 403.0300 | ASPHALT EMULSION TACK COAT | | 2.00000 | |
| | PLEASANT ST (PAVE2) | | | |
| | 14+88 TO 15+18 DRIVEWAY (PAVE2) | | | 34.00 |
| | 11+40 TO 12+30 LT GRAVEL PARKING APRON (PAVE2) | | | 30.00 |
| <u>Assembly: CONCRETE BLOCK PAVERS (PAVER) (Unit: SF Default Quantity: 3977.00)</u> | | | | |
| 202.0100 | EARTH EXCAVATION | 18" | 0.50000 | |
| 204.0100 | TRIMMING AND FINE GRADING | | 0.11111 | |
| 302.0100 | GRAVEL BORROW SUBBASE COURSE | 12" | 0.33333 | |
| 906.9901 | CONCRETE BLOCK PAVERS | | 1.00000 | |
| | PLEASANT ST (PAVER) | | | |
| | 15+31 TO 16+00 LT (PAVER) | | | 3977.00 |